

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260610 Call Order: 009 Proposal: T5886 District:05

Counties: LAKE

Road Name: SR 50 (BROAD ST)

Limits: FROM 2ND AVE TO SILVER EAGLE RD

Project(s): 42257035201(*) Federal Aid No: D517090B

Total Roadway Length:	1.847 Miles	Contract Days:	190
Total Bridge Length:	0.000 Miles	Letting Date:	06/10/26
Total Proposal Length:	1.847 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30 Days

Proposal Budget Estimate: \$3,467,315.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of Bike Path/Trail, Drainage Improvements, Signing/Pavement Markings on State Road 50, Eagles Crossing and CR 565A from Second Avenue to Silver Eagle Road, approximately 1.85 miles in Lake County

Call Order: 009 Proposal: T5886

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (42257035201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42257035201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (42257035201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	60.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	13,460.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,004.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	582,672.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	570.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,236.000
	0102-115-	TYPE III BARRICADE	ED	380.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	40.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	40.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	333.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,419.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	172.970
	0107- 2-	MOWING	AC	95.040
	0110- 1- 1	CLEARING & GRUBBING (42257035201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	5.120
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,262.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	3.000
	0110- 21-	TREE PROTECTION BARRIER	LF	8,136.000

Call Order: 009 Proposal: T5886

ALT	Item	Description	Unit	Quantity
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	137.000
	0120- 1-	REGULAR EXCAVATION	CY	7,122.400
	0120- 6-	EMBANKMENT	CY	6,302.300
	0160- 4-	TYPE B STABILIZATION	SY	14,186.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	11,301.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,516.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,495.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1,336.200
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	63.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	125.600
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	5.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	277.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	874.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	87.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	38.000
	0430-611-125	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	1.000
	0430-611-329	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 24"PIPE	EA	1.000
	0430-612-033	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 30"	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	12.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	36.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	492.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	17.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	220.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	23.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,038.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	643.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	177.000
	0527- 2-	DETECTABLE WARNINGS	SF	698.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	33,266.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,510.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42257035201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	34.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	17.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	24.000

Call Order: 009 Proposal: T5886

ALT	Item	Description	Unit	Quantity
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	143.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42257035201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	972.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	137.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	21.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.028