

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 007	Proposal: T2A44	District:02
Counties:	LEVY			
Road Name:	SR 45 (US 27)			
Limits:	FROM SR 500 (US 27) TO ALACHUA CO LINE			
Project(s):	21043255201(*)	Federal Aid No:	D225090B	
Total Roadway Length:	7.274 Miles	Contract Days:	240	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	7.274 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	
Proposal Budget Estimate:	\$6,943,867.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing of the existing travel lanes and shoulders, minor ADA upgrades, guardrail upgrades, drainage improvements, and signing and pavement marking updates.

Call Order: 007 Proposal: T2A44

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21043255201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21043255201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	14,104.000
	0102- 61-	BUSINESS SIGN	EA	1.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	875.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,725.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	64,479.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	159.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	813.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,272.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-115-	TYPE III BARRICADE	ED	639.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	160.000
	0104- 10- 3	SEDIMENT BARRIER	LF	10,028.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	502.300
	0107- 2-	MOWING	AC	432.070
	0110- 1- 1	CLEARING & GRUBBING (21043255201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	463.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	4.000
	0120- 1-	REGULAR EXCAVATION	CY	114.400

Call Order: 007 Proposal: T2A44

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	776.300
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	4,419.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	1,160.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	3,753.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	105,916.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,326.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	1,586.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	35,379.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	9,108.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	12,280.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	85.200
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	6.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	4.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	47.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	503.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-518-102	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
	0430-613-125	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,651.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	358.000
	0527- 2-	DETECTABLE WARNINGS	SF	318.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	6.400
	0530- 74-	BEDDING STONE	TN	8.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,056.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	3.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,952.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	27,745.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,466.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,627.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	14.444
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,716.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	249.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	406.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.221

Call Order: 007 Proposal: T2A44

ALT	Item	Description	Unit	Quantity
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.513
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.560
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21043255201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	18.172
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	26.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	15.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,627.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21043255201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.052
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.160
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	869.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	248.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	169.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.010
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	235.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	14.444
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.464
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.146
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.139
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.512
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.550
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	900.000