

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260520 Call Order: 005 Proposal: T2A66 District:02

Counties: LEVY

Road Name: SR 500 (US ALT 27) AND SR 49 (US 129)

Limits: AT CR 335A AND AT NW 30TH AVE

Project(s): 44556925201(*) Federal Aid No: D225095B

Total Roadway Length:	0.434 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	05/20/26
Total Proposal Length:	0.434 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$2,177,889.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, base work, shoulder treatment, and other incidental construction on SR 500 (US ALT27) At CR 335A & SR 49 (US 129) At NE 30TH Ave in Levy County.

Call Order: 005 Proposal: T2A66

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44556925201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44556925201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44556925201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44556925201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,145.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	2,317.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	2,066.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,680.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	54.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	1,488.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	6.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	870.000
	0102-115-	TYPE III BARRICADE	ED	861.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	108.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	108.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	210.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,068.000
	0107- 1-	LITTER REMOVAL	AC	31.750
	0107- 2-	MOWING	AC	27.680
	0110- 1- 1	CLEARING & GRUBBING (44556925201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,959.200
	0120- 6-	EMBANKMENT	CY	3,979.100
	0160- 4-	TYPE B STABILIZATION	SY	10,795.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,878.000

Call Order: 005 Proposal: T2A66

ALT	Item	Description	Unit	Quantity
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	1,907.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	3,146.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	120.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	5,230.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,233.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	1,225.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	9.900
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	141.800
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	907.600
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	279.600
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	59.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	1,139.500
	0350- 30- 13	CONCRETE PAVEMENT FOR ROUNDABOUT APRON, 12" DEPTH	SY	100.000
	0520- 2- 8	CONCRETE CURB, TYPE RA	LF	122.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,762.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.381
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	21.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.342
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44556925201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	1.602
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	15.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	15.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	8.000
	0700-141-122	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/2 BEACONS, 12-20 SF OF STATIC SIGN PANELS	EA	6.000
	0700-141-801	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, RELOCATE BEACON(S), SIGN TO REMAIN	EA	2.000
	0700-141-902	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - GROUND MOUNT	EA	6.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	341.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44556925201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	319.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	140.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.069
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	13.000

Call Order: 005 Proposal: T2A66

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	383.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.027
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.056
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.078
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.042
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.284
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.814
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	113.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	175.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	198.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000