

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260520 Call Order: 016 Proposal: T7609 District:07

Counties: HILLSBOROUGH

Road Name: SR 685 (US 41B / N FLORIDA AVE)

Limits: AT HANNA AVE

Project(s): 45429615201(*) Federal Aid No: D726014B

Total Roadway Length:	0.031 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	05/20/26
Total Proposal Length:	0.031 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days

Proposal Budget Estimate: \$411,500.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of pedestrian and ADA improvements at the intersection of SR 685 (North Florida Avenue) and Hanna Avenue, consisting of upgraded curb ramps, enhanced pedestrian signalization, pavement marking improvements, loop detector replacements, and full intersection resurfacing in Hillsborough County.

Call Order: 016 Proposal: T7609

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45429615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45429615201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45429615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,075.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,925.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	150.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	150.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	668.000
	0107- 1-	LITTER REMOVAL	AC	0.550
	0107- 2-	MOWING	AC	0.550
	0110- 1- 1	CLEARING & GRUBBING (45429615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	120.000
	0120- 6-	EMBANKMENT	CY	57.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45429615201)	LS	1.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	88.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,188.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	105.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	277.000

Call Order: 016 Proposal: T7609

ALT	Item	Description	Unit	Quantity
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	149.000
	0527- 2-	DETECTABLE WARNINGS	SF	160.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	85.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45429615201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	29.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45429615201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	549.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	24.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	63.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	252.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.082
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.008
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.083
Section 0003 Signalization				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	135.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	150.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	8.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000