

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260325	Call Order: 003	Proposal: T5876	District:05
Counties:	BREVARD			
Road Name:	SR 9 (I-95)			
Limits:	FROM INDIAN RIVER CO LINE TO BABCOCK ST			
Project(s):	45059515201(*)	Federal Aid No:	D525018B	
Total Roadway Length:	12.399 Miles	Contract Days:	500	
Total Bridge Length:	0.144 Miles	Letting Date:	03/25/26	
Total Proposal Length:	12.543 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$29,614,867.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Milling and Resurfacing, Shoulder Treatment, Guardrail, Signing and Pavement/Markings, Lighting, and Intelligent Transportation Systems (ITS) of I-95 from Indian River County line to Babcock St. 12.543 miles in Brevard County, Florida.

Call Order: 003 Proposal: T5876

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45059515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45059515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,340.000
	0102- 60-	WORK ZONE SIGN	ED	61,812.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	82,914.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	368.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,472.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	500.000
	0102-115-	TYPE III BARRICADE	ED	108.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	972.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	972.000
	0104- 10- 3	SEDIMENT BARRIER	LF	62,307.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	238.000
	0107- 1-	LITTER REMOVAL	AC	6,793.800
	0107- 2-	MOWING	AC	3,800.520
	0110- 1- 1	CLEARING & GRUBBING (45059515201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2.700
	0120- 6-	EMBANKMENT	CY	128.900
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	15,434.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	288,082.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	221,904.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	179,900.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	84,649.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	24,524.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	5,765.000

Call Order: 003 Proposal: T5876

ALT	Item	Description	Unit	Quantity
	0327- 70- 34	MILLING EXISTING ASPHALT PAVEMENT, 8" AVG DEPTH	SY	5,851.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	23,766.800
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	53,491.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	22,296.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	232.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,015.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	365.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	258.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	5.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	5.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,440.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	11.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	10.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	4.000
	0536- 85- 29	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	2.000
	0538- 1-	GUARDRAIL RESET	LF	1,771.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	57,436.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,145.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	146.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	165.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	13.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	13.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,742.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	25.580
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.984
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	903.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	52.175
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	25.095
	0922-334- 3	SUPERPAVE ASPHALTIC CONCRETE, THICK LIFT, TRAFFIC LEVEL E	TN	1,689.400
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	11.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45059515201)	LS	1.000

Call Order: 003 Proposal: T5876

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	47.138
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	34.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	28.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	4.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	12.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	12.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	4.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	8.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	8.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	58.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,670.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45059515201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	903.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	25.029
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.984
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	51.467
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	25.095
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.364
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.365
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.728
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	2,250.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	51,550.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,308.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	54.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	341.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	4.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	3.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	3.000

Call Order: 003 Proposal: T5876

ALT	Item	Description	Unit	Quantity
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (45059515201)	LS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	198,864.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	4,239.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	4.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	62.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	12.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	102.000
	0715- 61-442	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 12' ARM LENGTH	EA	142.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	247.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	4.000
	0715-512-145	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 45'	EA	3.000
Section 0004 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	12.543
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	3.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	439.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,132.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	201.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND, 2-12 FIBERS	LF	1,927.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	230.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	6.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	48.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	1.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	5.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	2.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	2.000
	0633- 3- 45	FIBER OPTIC CONNECTION HARDWARE, RELOCATE PATCH PANEL, PRETERMINATED	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	500.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	190.000
	0633- 8- 12	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, COMPOSITE	LF	768.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	19.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,938.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000

Call Order: 003 Proposal: T5876

ALT	Item	Description	Unit	Quantity
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	1.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	1.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	2.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	1.000
	0676- 2-600	ITS CABINET- REMOVE	EA	1.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	1.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	1.000
	0684- 2- 4	DEVICE SERVER, RELOCATE	EA	1.000
	0684- 7- 1	MANAGED HUB ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	3.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	3.000