

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250924	Call Order: 005	Proposal: T2A45	District:02
Counties:	COLUMBIA			
Road Name:	SR 10 (US 90)			
Limits:	AT SW HEATHRIDGE DR			
Project(s):	44333225201(*)	Federal Aid No:	D225042B	
Total Roadway Length:	0.284 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	0.284 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$932,587.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of left-turn lane widening, milling & resurfacing, base work, shoulder treatment, drainage improvements, highway signing and other incidental construction on SR 10 (US 90) at SW Heathridge Dr. in Columbia County.

Call Order: 005 Proposal: T2A45

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44333225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44333225201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44333225201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44333225201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,400.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	938.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,170.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	118.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	208.000
	0104- 10- 3	SEDIMENT BARRIER	LF	907.000
	0107- 1-	LITTER REMOVAL	AC	10.780
	0107- 2-	MOWING	AC	10.700
	0110- 1- 1	CLEARING & GRUBBING (44333225201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	502.000
	0120- 4-	SUBSOIL EXCAVATION	CY	227.100
	0120- 6-	EMBANKMENT	CY	637.600
	0160- 4-	TYPE B STABILIZATION	SY	1,992.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	493.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,007.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	5,018.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	187.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	534.800

Call Order: 005 Proposal: T2A45

ALT	Item	Description	Unit	Quantity
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	94.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	6.200
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,719.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,260.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.080
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	3.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.343
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	140.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44333225201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.773
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	3.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	124.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44333225201)	LS	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	140.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.570
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.777