

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 011	Proposal: T4717	District:04
Counties:	BROWARD			
Road Name:	SR 736 (DAVIE BLVD)			
Limits:	FROM SR 9 (I-95) TO SR 5 (US 1)			
Project(s):	44411815201(*)	Federal Aid No:	D425044B	
Total Roadway Length:	1.768 Miles	Contract Days:	232	
Total Bridge Length:	0.078 Miles	Letting Date:	12/03/25	
Total Proposal Length:	1.846 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$2,971,041.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, maintenance of traffic (standard, special detour, temporary signalization, temporary detection, officer), environmental (inlet protection), concrete (removal, sidewalk, prestressed service pole, CCTV pole), ITS (ITSFM, fiber optic cable, conduit, pull/splice box, video detection-Bluetooth, CCTV camera, Wireless Access Points, Arterial Dynamic Messaging Signs (ADMS), cabinets, field ethernet switches, RPMU (remote power management units), electrical (power service, service wire, service disconnect, uninterruptible power supply), and sod along State Road 736 (Davie Boulevard) from State Road 9 (I 95) to State Road 5 (US 1) for 1.846 miles in Broward County.

Call Order: 011 Proposal: T4717

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44411815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44411815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	8.000
	0102- 60-	WORK ZONE SIGN	ED	11,205.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,380.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	49,192.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	697.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	925.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,624.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,624.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	232.000
	0102-115-	TYPE III BARRICADE	ED	510.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	20.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44411815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44411815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	160.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	164.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	293.000
	0999- 16-	PARTNERING, DO NOT BID (44411815201)	LS	1.000

Call Order: 011 Proposal: T4717

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44411815201)	LS	1.000
Section 0002 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.846
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	7.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	334.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	9,874.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	350.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	467.000
	0632- 7- 7	SIGNAL CABLE, REMOVE- OUTSIDE OF INTERSECTION	LF	437.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND, 2-12 FIBERS	LF	1,545.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	12,912.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	108.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	6.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	14.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	72.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	6.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	6.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	3.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	232.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	438.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	29.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	8.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	10.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	6.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,153.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	6.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	8.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	5.000
	0643-600-	STRAIN POLE, WOOD, REMOVE	EA	1.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	3.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	3.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	4.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000

Call Order: 011 Proposal: T4717

ALT	Item	Description	Unit	Quantity
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	1.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	1.000
	0682- 1-153	ITS CCTV CAMERA, F&I, STATIONARY, IP, HIGH DEFINITION	EA	1.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	6.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	6.000
	0684- 1- 5	MANAGED FIELD ETHERNET SWITCH, ADJUST / MODIFY	EA	1.000
	0684- 6- 1	WIRELESS COMMUNICATION SYSTEM DEVICE, FURNISH & INSTALL	EA	4.000
	0684- 7- 5	MANAGED HUB ETHERNET SWITCH, ADJUST/MODIFY	EA	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	6.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	6.000
	0700- 8-135	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS, FULL COLOR, 51-100 SF	EA	2.000
	0700- 10-122	DMS SUPPORT STRUCTURE, CANTILEVER, 21-30 FT	EA	1.000
	0700- 10-123	DMS SUPPORT STRUCTURE, CANTILEVER, 31-40 FT	EA	1.000