

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT261202 Call Order: 003 Proposal: T1950 District:01
 Counties: POLK
 Road Name: SR 563 (MLK JR AVE)
 Limits: AT PEAR ST / PARKER ST AND FROM S OF SR 539 (KATHLEEN RD) TO SR 546 (US 92)

Project(s): 44627415201(*) Federal Aid No: D126067B
 Project(s): 45146915201 Federal Aid No: N/A
 Total Roadway Length: 0.595 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 12/02/26
 Total Proposal Length: 0.628 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Days
 Proposal Budget Estimate: \$1,520,109.00

Please read the full advertisement

Description:

The improvements under this project consist of milling and resurfacing, median modifications, sidewalk, curb ramps, and signing and pavement markings on SR 563 from South of SR 539 (Kathleen Road) to South of SR 546 (US 92) in Polk County.

Call Order: 003 Proposal: T1950

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44627415201)	LS	1.000
	0101- 1-	MOBILIZATION (45146915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44627415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45146915201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45146915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	76.000
	0102- 60-	WORK ZONE SIGN	ED	19,320.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	23,880.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,049.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	600.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	373.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,266.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-115-	TYPE III BARRICADE	ED	168.000
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	96.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	581.000
	0104- 10- 3	SEDIMENT BARRIER	LF	920.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	37.000
	0107- 1-	LITTER REMOVAL	AC	10.200
	0107- 2-	MOWING	AC	6.400

Call Order: 003 Proposal: T1950

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44627415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45146915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	608.000
	0120- 1-	REGULAR EXCAVATION	CY	47.200
	0120- 6-	EMBANKMENT	CY	28.900
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	77.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	21,657.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,809.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,793.200
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	66.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	544.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	140.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	221.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	134.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	16.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	344.000
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	287.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.279
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.147
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,411.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	20.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	276.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.775
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.117
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.034
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	45.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.362
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	25.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.107
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44627415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45146915201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	14.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000

Call Order: 003 Proposal: T1950

ALT	Item	Description	Unit	Quantity
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	18.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	2.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	421.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44627415201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45146915201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.100
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.080
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,412.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	20.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	276.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.034
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	46.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	140.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.107
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	69.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.276
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.047
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.775
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.117
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.410
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	84.000
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	30.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	120.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000