

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 008	Proposal: T2A89	District:02
Counties:	HAMILTON			
Road Name:	SR 93 (I-75)			
Limits:	FROM SR 6 TO N OF SR 143 (HAMILTON AVE)			
Project(s):	42463135201(*)	Federal Aid No:	D226019B	
Total Roadway Length:	5.886 Miles	Contract Days:	270	
Total Bridge Length:	0.000 Miles	Letting Date:	12/02/26	
Total Proposal Length:	5.886 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$21,590,678.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, shoulder treatment, highway signing, guardrail, pier protection and other incidental construction on I-75 (SR93) in Hamilton County from SR 6 to north of SR 143(HAMILTON AVE).

Call Order: 008 Proposal: T2A89

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	158.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	44.400
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42463135201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42463135201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	5,400.000
	0102- 60-	WORK ZONE SIGN	ED	17,700.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,908.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	46,849.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	750.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	9,415.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	6.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,396.000
	0102-115-	TYPE III BARRICADE	ED	360.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,080.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,080.000
	0107- 1-	LITTER REMOVAL	AC	1,700.800
	0107- 2-	MOWING	AC	1,458.590
	0110- 1- 1	CLEARING & GRUBBING (42463135201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	120.000
	0120- 1-	REGULAR EXCAVATION	CY	1,118.400
	0120- 6-	EMBANKMENT	CY	54.200
	0160- 4-	TYPE B STABILIZATION	SY	967.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	967.000

Call Order: 008 Proposal: T2A89

ALT	Item	Description	Unit	Quantity
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	22,263.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	14,428.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	130,059.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	97,536.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	5,467.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	160,777.000
	0327- 70- 31	MILLING EXISTING ASPHALT PAVEMENT, 7 1/2" AVG DEPTH	SY	1,337.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	11,641.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	38,837.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	10,506.600
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	2,427.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	744.000
	0431- 1-124	PIPE LINER, CURED IN PLACE, 24"	LF	58.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	1,183.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	3,605.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	1,961.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	6.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	6.000
	0536- 73-	GUARDRAIL REMOVAL	LF	5,770.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	42,803.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	117.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	154.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	193.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 11	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 1 LOOP	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	3.000
	0695- 9- 11	TRAFFIC MONITORING SITE WEIGH- IN- MOTION ELECTRONIC SENSOR, FURNISH & INSTALL, WITH SPECIAL FOUNDATION SOCKET	EA	8.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.341
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.686
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,190.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	44.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	25.587
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	14.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.584

Call Order: 008 Proposal: T2A89

ALT	Item	Description	Unit	Quantity
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	116.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.084
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42463135201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	23.098
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	43.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	9.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	48.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	3.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	16.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	4.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	111.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,279.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42463135201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,129.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	44.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	14.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	124.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.039
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	12.118
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.434
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	24.608
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	12.123
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.263
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.272
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.500
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.085
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.085

Call Order: 008 Proposal: T2A89

ALT	Item	Description	Unit	Quantity
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	451.000
Section 0004 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	270.000