

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260429 Call Order: 001 Proposal: T2809 District:02
Counties: LAFAYETTE
Road Name: CAMP GRADE RD AND SR 51
Limits: OVER STEINHATCHEE RIVER BRIDGE AND OVER BRITT CREEK
Project(s): 43742615201(*) Federal Aid No: D220079B
Project(s): 44514815201 Federal Aid No: D225097B
Total Roadway Length: 0.090 Miles Contract Days: 600
Total Bridge Length: 0.064 Miles Letting Date: 04/29/26
Total Proposal Length: 0.154 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 60 Days

Proposal Budget Estimate: \$10,719,626.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of bridge construction, guardrail, milling and resurfacing, base work, stabilization, drainage improvements, steel sheet pile walls, temporary portable signals, and other incidental construction on SR 51 over Britt Creek and Camp Grade Road over Steinhatchee River in Lafayette County.

Call Order: 001 Proposal: T2809

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43742615201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44514815201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (Bridge No. 334001)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	122.200
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	145.500
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	147.000
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	7.200
	0400- 7- 1	BRIDGE DECK GROOVING	SY	507.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	507.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	17.900
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	10.500
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	30,512.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	15,213.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	370.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	21,297.000
	0450- 8- 11	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12" CARBON STEEL, WIDTH 48-51"	LF	1,025.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE	LF	1,190.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	61.000
	0455- 35- 6	STEEL PILING, HP 14 X 89	LF	3,060.000
	0455-115-	PILE REDRIVE	EA	23.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	3,126.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	61.000

Call Order: 001 Proposal: T2809

ALT	Item	Description	Unit	Quantity
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	61.000
	0455-144- 6	TEST PILES - STEEL, HP 14 x 89	LF	1,195.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	166.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	200.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	3,000.000
	0460- 1-100	STRUCTURAL STEEL - REHABILITATE HISTORIC BRIDGE ELEMENTS, PROJECT 437426-1-52-01 (43742615201. Bridge No. 334026)	LS	1.000
	0460- 2- 1	STRUCT STEEL, CARBON (43742615201)	LS	1.000
	0460- 2- 1	STRUCT STEEL, CARBON (43742615201. Bridge No. 334026)	LS	1.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43742615201. Bridge No. 334026)	LS	1.000
	0460- 71- 2	METAL TRAFFIC RAILING, STEEL POST AND RAIL	LF	450.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	34.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	320.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	8.500
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	688.400
	0530- 74-	BEDDING STONE	TN	240.100
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	960.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	4.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43742615201)	LS	1.000
	0101- 1-	MOBILIZATION (44514815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43742615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44514815201)	LS	1.000
	0102- 2-142	SPECIAL DETOUR- TEMPORARY BRIDGE, PROJECT 445148-1-52-01 (44514815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44514815201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44514815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	58,840.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,930.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,730.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	42,196.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	20.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	7,158.000
	0102-115-	TYPE III BARRICADE	ED	9,240.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO- LANE, TWO-WAY ROADWAYS	ED	320.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	320.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	400.000
	0103- 1-100	TEMPORARY WORK STRUCTURE (43742615201)	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,546.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	268.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	2,365.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000

Call Order: 001 Proposal: T2809

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	48.060
	0107- 2-	MOWING	AC	41.180
	0110- 1- 1	CLEARING & GRUBBING (43742615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44514815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	8.000
	0110- 21-	TREE PROTECTION BARRIER	LF	75.000
	0120- 1-	REGULAR EXCAVATION	CY	680.500
	0120- 6-	EMBANKMENT	CY	2,512.600
	0160- 4-	TYPE B STABILIZATION	SY	4,543.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,580.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,830.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	308.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	446.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	26.200
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	12.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	491.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	55.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	6.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	11,733.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	1,343.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	709.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	18.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	732.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	11.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	116.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	514.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, APPROACH TL-2	EA	1.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, APPROACH TL-3	EA	3.000
	0536- 73-	GUARDRAIL REMOVAL	LF	237.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	6.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	11,299.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,092.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.064
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	92.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.040
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43742615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44514815201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.717
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000

Call Order: 001 Proposal: T2809

ALT	Item	Description	Unit	Quantity
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	80.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44514815201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	10.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.552
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.530
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.042
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.042