

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 006	Proposal: T3958	District:03
Counties:	GULF			
Road Name:	VICTORIA AVE			
Limits:	OVER TIDAL BRANCH, BRIDGE NO 514060			
Project(s):	44117915201(*)	Federal Aid No:	D325026B	
Total Roadway Length:	0.028 Miles	Contract Days:	315	
Total Bridge Length:	0.006 Miles	Letting Date:	12/03/25	
Total Proposal Length:	0.034 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	

Proposal Budget Estimate: \$1,144,996.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of Victoria Avenue over Tidal Branch Bridge No. 514060, remove and replace existing bridge with new bridge No. 514080, approach slabs, roadway reconstruction and widening, drainage, guardrail, sod, signing and pavement marking in Gulf County.

Call Order: 006 Proposal: T3958

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44117915201)	LS	1.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	177.000
	0415- 10- 4	FIBER REINFORCED POLYMER BARS, #4 BAR	LF	1,182.000
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	8,846.000
	0415- 10- 6	FIBER REINFORCED POLYMER BARS, #6 BAR	LF	384.000
	0415- 10- 7	FIBER REINFORCED POLYMER BARS, #7 BAR	LF	6,456.000
	0415- 10- 8	FIBER REINFORCED POLYMER BARS, #8 BAR	LF	16,416.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	193.900
	0530- 74-	BEDDING STONE	TN	72.200
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44117915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44117915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,190.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,520.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	630.000
	0102-115-	TYPE III BARRICADE	ED	2,520.000
	0104- 10- 3	SEDIMENT BARRIER	LF	378.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	214.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	126.000
	0110- 1- 1	CLEARING & GRUBBING (44117915201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	98.200
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	51.800
	0160- 4-	TYPE B STABILIZATION	SY	521.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	163.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	339.000

Call Order: 006 Proposal: T3958

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	102.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	27.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	48.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.500
	0460- 71-101	METAL TRAFFIC RAILING, CULVERT HEADWALL ATTACHED	LF	131.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	106.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	44.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	231.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	32.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	99.000
Section 0003 Signing				
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	10.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44117915201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.068
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.068