

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 016	Proposal: T5873	District:05
Counties:	MARION			
Road Name:	SR 200 (SW COLLEGE RD)			
Limits:	AT SW 60TH AVE			
Project(s):	45125315201(*)	Federal Aid No:	D525002B	
Total Roadway Length:	0.100 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	0.100 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	

Proposal Budget Estimate: \$1,010,155.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of intersection safety improvements including signalization and lighting improvements, minor sidewalk improvements (including detectable warnings), and signing and pavement markings at the intersection of SR 200 (SW College Rd.) and SW 60th Ave. in Marion County.

Call Order: 016 Proposal: T5873

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45125315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45125315201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45125315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	68.000
	0102- 60-	WORK ZONE SIGN	ED	2,755.000
	0102- 61-	BUSINESS SIGN	EA	4.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,559.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	4,704.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	84.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	473.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	100.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	100.000
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.041
	0104- 10- 3	SEDIMENT BARRIER	LF	904.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	13.000
	0107- 1-	LITTER REMOVAL	AC	2.760
	0107- 2-	MOWING	AC	2.020
	0110- 1- 1	CLEARING & GRUBBING (45125315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	103.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	17.300
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	34.000
	0520- 1-110	CONCRETE CURB & GUTTER, TYPE F, WITH CLASS IV CONCRETE, PROJECT 451253-1-52-01	LF	90.000

Call Order: 016 Proposal: T5873

ALT	Item	Description	Unit	Quantity
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	71.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	5.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	23.000
	0522- 2-102	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK, WITH CLASS IV CONCRETE, PROJECT 451253-1-52-01	SY	69.000
	0527- 2-	DETECTABLE WARNINGS	SF	60.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	107.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45125315201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	8.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	6.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8"	LF	87.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT	LF	313.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	25.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK	LF	126.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.019
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	229.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	16.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	22.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	5,067.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 61-321	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 10' ARM LENGTH	EA	3.000
	0715- 62-321	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT, 10' ARM LENGTH	EA	2.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	3.000
	0715- 66-366	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT, 16' ARM LENGTH	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	10.000
Section 0004 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.100
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,259.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	740.000

Call Order: 016 Proposal: T5873

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	369.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	24.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	141.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	5.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 1- 17	STEEL STRAIN POLE, F&I, TYPE PS- X	EA	2.000
	0650- 1- 24	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 3 SECTION, 1 WAY	AS	16.000
	0650- 1- 29	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W ALUMIN, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0660- 9- 11	TRAFFIC DATA DETECTION SYSTEM- VIDEO, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	2.000
	0660- 9- 12	TRAFFIC DATA DETECTION SYSTEM- VIDEO, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	6.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0700-141-111	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0700-141-360	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, BLANK OUT SIGN <12 SF	EA	2.000