

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260128	Call Order: 002	Proposal: T1922	District:01
Counties:	MANATEE			
Road Name:	SR 684 (CORTEZ RD)			
Limits:	FROM 86TH ST W TO W OF 30TH ST W			
Project(s):	44504415201(*)	Federal Aid No: D125064B		
Project(s):	44504415203	Federal Aid No: D125064B		
Total Roadway Length:	3.479 Miles	Contract Days:	375	
Total Bridge Length:	0.000 Miles	Letting Date:	01/28/26	
Total Proposal Length:	3.479 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	

Proposal Budget Estimate: \$12,831,170.00

Please read the full advertisement

Description:

The work under this project consists of milling and resurfacing, drainage improvements, curb and gutter, sidewalks, signalization, lighting, and signing and pavement marking on SR 684 (Cortez Rd) from 86th Street West to West of 30th Street West in Manatee County.

Call Order: 002 Proposal: T1922

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44504415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44504415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44504415201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44504415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	460.000
	0102- 60-	WORK ZONE SIGN	ED	123,129.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,104.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,548.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	591,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	46,190.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	3,253.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	750.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,340.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,750.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,750.000
	0102-115-	TYPE III BARRICADE	ED	10,480.000
	0104- 10- 3	SEDIMENT BARRIER	LF	556.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	97.000
	0107- 1-	LITTER REMOVAL	AC	270.780
	0107- 2-	MOWING	AC	199.070
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44504415201)	LS	1.000

Call Order: 002 Proposal: T1922

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44504415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44504415203)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,165.000
	0120- 1-	REGULAR EXCAVATION	CY	739.500
	0120- 6-	EMBANKMENT	CY	1,417.000
	0160- 4-	TYPE B STABILIZATION	SY	3,224.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	14.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	3,210.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	907.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	383.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	99,106.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	35,247.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	7,348.500
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	9,534.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3.400
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	5.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	6.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	5.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	2.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	2.000
	0425- 1-455	INLETS, CURB, TYPE J-5, PARTIAL	EA	5.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	2.000
	0425- 1-465	INLETS, CURB, TYPE J-6, PARTIAL	EA	1.000
	0425- 1-523	INLETS, DT BOT, TYPE C, JBOT, <10'	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 1-715	INLETS, GUTTER, TYPE V, PARTIAL	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	3.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	1.000
	0425- 2- 93	MANHOLES, J-8, PARTIAL	EA	1.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	357.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	74.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	417.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	311.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	13.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	187.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	65.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	4.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	1.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	1.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	3.000
	0440- 1- 10	UNDERDRAIN, TYPE I	LF	250.000

Call Order: 002 Proposal: T1922

ALT	Item	Description	Unit	Quantity
	0440- 70-	UNDERDRAIN INSPECTION BOX	EA	2.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	30.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	5,646.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,614.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	458.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	178.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	42.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	79.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	1,183.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	240.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	290.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	619.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,011.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,019.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,427.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	9,808.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	20.236
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.044
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	7,489.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	626.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	7,430.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	10.039
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.954
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	323.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.472
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	524.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.306
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44504415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44504415203)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	88.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	16.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	12.000

Call Order: 002 Proposal: T1922

ALT	Item	Description	Unit	Quantity
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	25.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	9.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	88.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	6.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	55.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	14.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,552.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	310.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44504415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,967.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	626.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,524.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.592
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	241.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	260.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.927
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	4,646.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	8.669
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.992
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.092
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.051
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	68.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	276.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	1.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,156.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,561.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	8.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	14.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	8.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	133.000

Call Order: 002 Proposal: T1922

ALT	Item	Description	Unit	Quantity
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	8.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	7.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	115.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	84.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	39.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	5.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	13.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	2.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	7.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	63.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	18.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	4.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	56.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	34.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	17.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	7.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	48.000
	0660- 3- 51	VEHICLE DETECTION SYSTEM- MICROWAVE, ADJUST & MODIFY, CABINET EQUIPMENT	EA	3.000
	0660- 4- 62	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE ABOVE GROUND EQUIPMENT	EA	7.000
	0660- 9- 41	TRAFFIC DATA DETECTION SYSTEM- VIDEO, RELOCATE, CABINET EQUIPMENT	EA	1.000
	0660- 9- 42	TRAFFIC DATA DETECTION SYSTEM- VIDEO, RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	56.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	2.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	29.000
	0670- 5-160	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK	AS	8.000

Call Order: 002 Proposal: T1922

ALT	Item	Description	Unit	Quantity
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	8.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	2.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	2.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	8.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	19.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	30.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	23.000
Section 0005 Intelligent Transportation System				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	10.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	263.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	502.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,786.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	32.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	96.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	8.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	8.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	8.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	375.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	14.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	8.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	3.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	3.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	4.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	10.000
	0684- 1- 6	MANAGED FIELD ETHERNET SWITCH, REMOVE- CABINET TO REMAIN	EA	2.000
	0924-681- 1	CONNECTED VEHICLE ROADSIDE EQUIPMENT, RSU	EA	10.000