

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 005	Proposal: T2A31	District:02
Counties:	DUVAL			
Road Name:	SR 10 (ATLANTIC BLVD)			
Limits:	FROM E OF LAURINA ST TO SILVERSMITH CREEK BRIDGE			
Project(s):	43930215201(*)	Federal Aid No:	D225041B	
Total Roadway Length:	0.064 Miles	Contract Days:	90	
Total Bridge Length:	0.029 Miles	Letting Date:	07/30/25	
Total Proposal Length:	0.093 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$780,048.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, curb & gutters, traffic separators, hand railings, curb ramps, sidewalk/bicycle path and other incidental construction on SR10 (Atlantic Blvd) Sidewalk from East of Laurina St to Silversmith Creek Bridge in Duval County.

Call Order: 005 Proposal: T2A31

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43930215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43930215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,840.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,430.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,440.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	270.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	194.000
	0102-115-	TYPE III BARRICADE	ED	720.000
	0104- 10- 3	SEDIMENT BARRIER	LF	981.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	527.000
	0107- 1-	LITTER REMOVAL	AC	2.860
	0107- 2-	MOWING	AC	2.460
	0110- 1- 1	CLEARING & GRUBBING (43930215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	21.000
	0120- 1-	REGULAR EXCAVATION	CY	5.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	7.500
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,149.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	259.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	151.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	82.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	163.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	85.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	98.000

Call Order: 005 Proposal: T2A31

ALT	Item	Description	Unit	Quantity
	0527- 2-	DETECTABLE WARNINGS	SF	35.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	32.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	198.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.186
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.372
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43930215201)	LS	1.000
Section 0002 Signing				
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	9.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	113.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	13.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43930215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	70.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	144.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.186
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.186
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.312