Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	07261209	Call Order: 004	Proposal: E7U80		District:07
Counties:	PINELLAS				
Road Name:	SR 595/SR 60/SR 586/US 19 - BRIDGE-REPAIR/REHABILITATION				
Limits:	15009000				
Project(s):	44998415201(*)		Federal Aid No: N/A		
Total Roadway Length:		0.727 Miles		Contract Days:	290
Total Bridge Length:		0.656 Miles		Letting Date:	12/09/26
Total Proposal Length:		1.383 Miles		Contract Execution Days:	10
				Special Start Date:	N/A
				Aquis/Flexible Start Time:	120 Days Flex Start
Proposal Budget Estimate:			$2,602,045.00		

Please read the full advertisement

Description:

The Improvements under this Contract consist of bridge repairs at Bridge Nos. 150042 (SR 595/Alternate US 19 over Pinellas Trail), 150043 (SR 60 over Clearwater Harbor), 150001 and 150074 (SR 595/Alternate US 19 over Long Bayou), and 150220 (SR 586 over Lake Tarpon Canal). The work consists of cleaning and sealing bridge decks on all listed bridges; spall repairs on Bridge Nos. 150042, 150043, 150001, and 150074; bridge jacking, bearing reset, and structural steel repairs on Bridge No. 150042; and partial-depth deck removal with latex overlay on Bridge Nos. 150001 and 150074, in Pinellas County.

Prequalification required.

Note the Substituted Commercial General Liability Insurance requirements contained in section(s) 7-13.2 and 7-13.4 of the project Specifications.

Call Order: 004 Proposal: E7U80

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400-140- 1	NEOPRENE PAD REPLACEMENT, BENT/PIER	EA	10.000
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	3.500
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	33.900
	0405- 70- 9	LATEX MODIFIED CONCRETE, VERY EARLY STRENGTH	CF	969.100
	0413-151-	METHACRYLATE MONOMER	GA	2,188.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	198,787.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	68.000
	0458- 1- 28	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITHOUT BACKER ROD	LF	96.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	8,370.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	100.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44998415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44998415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,522.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,946.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	25,708.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	119.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	372.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	1.160
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.340
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	1.510
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.330
	0926-102- 1	TEMPORARY PEDESTRIAN ACCESS	SFD	5,000.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44998415201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	200.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.350
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.500
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.340
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.500
Section 0004 Intelligent Transportation System				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	72.000