

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250827	Call Order: 009	Proposal: T4728	District:04
Counties:	BROWARD			
Road Name:	N 22ND AVE (SW 12TH AVE)			
Limits:	FROM SHERIDAN ST TO STIRLING RD			
Project(s):	44552615201(*)	Federal Aid No:	D425030B	
Project(s):	44552615202	Federal Aid No:	N/A	
Total Roadway Length:	1.027 Miles	Contract Days:	269	
Total Bridge Length:	0.000 Miles	Letting Date:	08/27/25	
Total Proposal Length:	1.027 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$2,964,437.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, signing and pavement marking improvements including the addition of sharrow pavement markings, curb ramp and sidewalk upgrades to meet current ADA criteria, introduce traffic calming features which include speed tables and raised intersections and roadway lighting along N 22nd Avenue/SW 12th Avenue from Sheridan Street (MP 0.000) to Stirling Road (MP 1.027) in the City of Hollywood and City of Dania Beach in Broward County.

Call Order: 009 Proposal: T4728

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44552615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44552615201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	80.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	28.000
	0102- 60-	WORK ZONE SIGN	ED	29,817.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,517.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	10,874.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	860.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	538.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	538.000
	0102-115-	TYPE III BARRICADE	ED	336.000
	0104- 10- 3	SEDIMENT BARRIER	LF	8,877.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	35.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44552615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44552615201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.080
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,478.000
	0110- 21-	TREE PROTECTION BARRIER	LF	415.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	11.000

Call Order: 009 Proposal: T4728

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	102.400
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44552615201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	242.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	575.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	288.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	20,199.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	288.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	1,713.900
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	2.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	19.000
	0425- 6- 1	METER BOXES, ADJUST	EA	3.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	8.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	30.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	63.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	610.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	3.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,967.000
	0523- 3-	PATTERNED PAVEMENT	SY	158.000
	0527- 2-	DETECTABLE WARNINGS	SF	874.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,082.000
	0999- 16-	PARTNERING, DO NOT BID (44552615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44552615201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44552615202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	44.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	12.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	26.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	450.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44552615201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	546.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	309.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.045
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	27.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	14.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	269.000

Call Order: 009 Proposal: T4728

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.101
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	165.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	40.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	39.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.710
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.977
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.595
Section 0003 Lighting				
	0715-511-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 35'	EA	40.000
	0715-550-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, REMOVE	EA	3.000
Section 0004 Signalization				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000