



**Call Order: 005 Proposal: T3981**

ALT	Item	Description	Unit	Quantity
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,510.700
	0530- 74-	BEDDING STONE	TN	562.400
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	3,600.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	18.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43938315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43938315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	20,250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,500.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,625.000
	0102-115-	TYPE III BARRICADE	ED	3,000.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,160.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,290.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	495.000
	0110- 1- 1	CLEARING & GRUBBING (43938315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,214.000
	0120- 4-	SUBSOIL EXCAVATION	CY	538.300
	0120- 5-	CHANNEL EXCAVATION	CY	1,158.900
	0120- 6-	EMBANKMENT	CY	5,898.900
	0160- 4-	TYPE B STABILIZATION	SY	3,123.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	853.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,807.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	193.100
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	238.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	16.300
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	4.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	82.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	64.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	358.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,218.000
<b>Section 0003 Signing</b>				
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	0.294
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.294
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	66.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.204
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.204