

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 015	Proposal: T3A21	District:03
Counties:	BAY			
Road Name:	SR 75 (US 231) FROM S OF SR 20 TO JACKSON COUNTY LINE			
Limits:	46040000			
Project(s):	45293715201(*)	Federal Aid No:	D326037B	
Project(s):	45293715203	Federal Aid No:	N/A	
Total Roadway Length:	9.737 Miles	Contract Days:	310	
Total Bridge Length:	0.009 Miles	Letting Date:	10/28/26	
Total Proposal Length:	9.827 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	
Proposal Budget Estimate:	\$12,666,441.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of 452937-1-52-01: milling and resurfacing, drainage, signalization, structures and signing and pavement marking improvements on SR 75 (US 231) from south of SR 20 to the Jackson County line; 452937-1-52-03 approach slab repair of Bridge No. 460080 over Juniper Creek. All work to be done in Bay County.

Call Order: 015 Proposal: T3A21

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0101- 1-	MOBILIZATION (45293715203)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45293715203)	LS	1.000
	0403- 1-100	EPOXY CONCRETE OVERLAY FOR CONCRETE BRIDGE DECKS	SY	90.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45293715203)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45293715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45293715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,100.000
	0102- 60-	WORK ZONE SIGN	ED	29,288.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	59,012.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	12,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	310.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	12,736.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,268.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	310.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	310.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	620.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	620.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,039.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	34.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	92.000

Call Order: 015 Proposal: T3A21

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	3,496.610
	0107- 2-	MOWING	AC	3,391.810
	0110- 1- 1	CLEARING & GRUBBING (45293715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	157.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,120.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45293715201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	779.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	718.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	631.300
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	68,901.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	47,606.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,698.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	2,676.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	42,999.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	233,396.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	29,144.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	10,991.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	13,705.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	89.700
	0431- 1-299	PIPE LINER- SPRAY APPLICATION, 61" AND GREATER	LF	337.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	164.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	96.000
	0527- 2-	DETECTABLE WARNINGS	SF	155.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	536.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	266.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0546- 71- 2	RAISED RUMBLE STRIP SET- SHORT TERM	EA	16.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	53,687.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	548.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	42.286
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.387
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,040.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	3,305.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,313.000

Call Order: 015 Proposal: T3A21

ALT	Item	Description	Unit	Quantity
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	38.318
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	5.433
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	368.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	36.846
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	876.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.890
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.234
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45293715201)	LS	1.000
Section 0003 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	16.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	22.806
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	83.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	18.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	36.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	73.000
	0700-142-131	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, WEDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	31.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	34.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	58.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	6,368.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45293715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,040.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,305.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,313.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	5.433
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	368.000

Call Order: 015 Proposal: T3A21

ALT	Item	Description	Unit	Quantity
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	60.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	876.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.234
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	27.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	151.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	15.838
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.992
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	16.550
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	10.098
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.305
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.395
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.609
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	8.325
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.890
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	2,681.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.162
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.162
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.162
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.162
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	790.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	329.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	500.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000