

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260325 Call Order: 005 Proposal: T1919 District:01
 Counties: CHARLOTTE
 Road Name: SR 35 (US 17)
 Limits: FROM S OF PINEGROVE CR TO N OF WASHINGTON LOOP RD
 Project(s): 45110415201(*) Federal Aid No: D125102B
 Total Roadway Length: 1.964 Miles Contract Days: 300
 Total Bridge Length: 0.131 Miles Letting Date: 03/25/26
 Total Proposal Length: 2.095 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Days

Proposal Budget Estimate: \$8,766,279.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutter, guardrail, sidewalks, bridge joints, traffic railing, lighting and signing and pavement markings on State Road 35 (US 17) from south of Pinegrove Circle to north of Washington Loop Road, in Charlotte County.

Call Order: 005 Proposal: T1919

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	990.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	120.400
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45110415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45110415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45110415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45110415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	245.800
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45110415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	300.000
	0102- 60-	WORK ZONE SIGN	ED	20,816.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,856.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,100.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,725.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	675.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	625.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	82,944.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	205,632.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	600.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	6.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	714.000

Call Order: 005 Proposal: T1919

ALT	Item	Description	Unit	Quantity
	0102-115-	TYPE III BARRICADE	ED	121.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,200.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,200.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	10.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,861.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,203.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	69.000
	0107- 1-	LITTER REMOVAL	AC	299.580
	0107- 2-	MOWING	AC	263.730
	0110- 1- 1	CLEARING & GRUBBING (45110415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,290.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	6.000
	0120- 1-	REGULAR EXCAVATION	CY	3,442.500
	0120- 6-	EMBANKMENT	CY	3,224.400
	0160- 4-	TYPE B STABILIZATION	SY	7,652.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,136.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	114.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,680.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,636.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	68,533.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	4,077.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	14,220.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	3,055.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	69.900
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	3.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	18.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	15.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	6.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0443- 72- 14	FRENCH DRAIN- AGGREGATE WITHOUT PIPE, 4-4.9' DEPTH	SY	30.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	162.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	4,522.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	704.000
	0520- 1- 24	CONCRETE CURB & GUTTER, TYPE E WITH SPECIAL PROFILE	LF	25.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	83.000
	0521- 72- 41	SHOULDER CONCRETE BARRIER, RETAINING SECTION	LF	120.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,631.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,033.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	374.000
	0527- 2-	DETECTABLE WARNINGS	SF	537.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	55.000

Call Order: 005 Proposal: T1919

ALT	Item	Description	Unit	Quantity
	0530- 74-	BEDDING STONE	TN	39.500
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,867.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	9.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	6.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	103.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	7.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	13.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	108.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	26,571.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,511.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.929
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.308
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,711.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	194.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	396.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.024
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.551
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	87.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.147
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	455.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.480
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45110415201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	5.970
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	67.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	13.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	44.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	35.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	1.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	14.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	18.000

Call Order: 005 Proposal: T1919

ALT	Item	Description	Unit	Quantity
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,928.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45110415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,426.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	194.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	224.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.551
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	81.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	262.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	455.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.480
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	4.382
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.292
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.024
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	3.540
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.022
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.016
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.185
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.138
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.138
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.138
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.138
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	826.000
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,038.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,671.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	8,613.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,191.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	7,591.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000

Call Order: 005 Proposal: T1919

ALT	Item	Description	Unit	Quantity
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	11.000
	0715- 61-411	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 8' ARM LENGTH	EA	11.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	11.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	11.000