

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	CT250924	Call Order: 009	Proposal: T4752	District:04
Counties:	BROWARD			
Road Name:	SR 858 HALLANDALE BEACH BLVD			
Limits:	FROM E OF SR 7 (US 441) TO SW 44TH AVE			
Project(s):	44754815201(*)	Federal Aid No: D425059B		
Total Roadway Length:	1.212 Miles	Contract Days:	68	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	1.212 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$318,253.00			

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of , but are not limited to, MOT (standard, pedestrian LCD, Arrow Board, PCMS), concrete (removal, sidewalk, driveways), and lighting (conduit, fiber optic, pull/splice box, electrical power service, electrical service wire, prestressed pole, conductors, load center, load center remove, luminaire, pole complete, cable distribution) along State Road 858 (Hallandale Beach Boulevard) from east of State Road 7 (US 441) to SW 44th Avenue for 1.212 miles in the City of West Park and the Town of Pembroke Park, Broward County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtml>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/construction/training/ctqp/smallbusiness/smallbusinessstraining.shtml>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 009 Proposal: T4752**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44754815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44754815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,244.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,040.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,726.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	68.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	164.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	38.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	38.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44754815201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	20.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	398.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	68.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	131.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,033.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	44.000
	0715- 61-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	3.000