

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 016	Proposal: T3A25	District:03
Counties:	SANTA ROSA			
Road Name:	SR 8 (I-10)			
Limits:	FROM MILLER BLUFF RD TO OKALOOSA COUNTY LINE			
Project(s):	45417915201(*)	Federal Aid No:	D326051B	
Total Roadway Length:	5.605 Miles	Contract Days:	325	
Total Bridge Length:	0.000 Miles	Letting Date:	10/28/26	
Total Proposal Length:	5.605 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	
Proposal Budget Estimate:	\$16,139,311.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, drainage improvements, highway signing, high tension cable barrier installation, ITS and other incidental construction on SR 8 (1-10) from Miller Bluff Road to the Okaloosa County line in Santa Rosa County.

Call Order: 016 Proposal: T3A25

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45417915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45417915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,640.000
	0102- 60-	WORK ZONE SIGN	ED	10,920.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	63,496.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	464.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	678.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	928.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	928.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	441.000
	0104- 10- 3	SEDIMENT BARRIER	LF	20,531.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	48.000
	0107- 1-	LITTER REMOVAL	AC	2,058.160
	0107- 2-	MOWING	AC	1,877.960
	0110- 1- 1	CLEARING & GRUBBING (45417915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	123.000
	0120- 1-	REGULAR EXCAVATION	CY	33.400
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	326.600
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45417915201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	791.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	495.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	87,602.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	83,017.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	82,751.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	14,114.700

Call Order: 016 Proposal: T3A25

ALT	Item	Description	Unit	Quantity
	0334- 1- 59	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, HIGH POLYMER	TN	13,653.800
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	7,003.900
	0425- 1-705	INLETS, GUTTER, TYPE S, PARTIAL	EA	14.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	54.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	59,441.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	5,129.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	280.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	14,258.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	29,884.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,508.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	11.224
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	11.224
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	11.226
	0904-540- 13	HIGH TENSION CABLE BARRIER SYSTEM - LENGTH OF NEED SEGMENT	LF	28,824.000
	0904-540- 14	HIGH TENSION CABLE BARRIER SYSTEM - END TERMINAL	EA	18.000
	0904-540- 15	HIGH TENSION CABLE BARRIER SYSTEM, END TERMINAL FOUNDATION- MISCELLANEOUS DRILLED SHAFT	CY	144.000
	0904-540- 16	HIGH TENSION CABLE BARRIER SYSTEM, CONCRETE MOW STRIP	LF	28,734.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45417915201)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	22.448
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,508.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45417915201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	11.224
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	11.224
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	11.226
Section 0003 Intelligent Transportation System				
	0102-112-	EXISTING ITS MAINTENANCE	DA	325.000
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	5.605
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5,105.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	30.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	735.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	4.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	12.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	1.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	1.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000

Call Order: 016 Proposal: T3A25

ALT	Item	Description	Unit	Quantity
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	325.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	1.000
	0639- 1-500	ELECTRICAL POWER SERVICE, ADJUST/MODIFY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	4,529.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0639- 6-121	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0649- 2-150	STEEL CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 50'	EA	1.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	1.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	1.000