

Call Order: 018 Proposal: T3964

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	32.000
	0107- 1-	LITTER REMOVAL	AC	866.780
	0107- 2-	MOWING	AC	773.890
	0110- 1- 1	CLEARING & GRUBBING (45080615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	151.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	8.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	620.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45080615201)	LS	1.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	13.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	352.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	99,558.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	20,493.000
	0327- 70- 10	MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH	SY	67,144.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	4,771.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	23,593.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	16,493.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	629.300
	0400- 1- 30	CONCRETE, CLASS I (SEAL)	CY	0.400
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	10.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	48.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	142.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	19.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	112.000
	0527- 2-	DETECTABLE WARNINGS	SF	85.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	6,693.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	51.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	11.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	1.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	5,763.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	34.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	31,670.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,844.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	22.806
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	989.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	60.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,161.000

Call Order: 018 Proposal: T3964

ALT	Item	Description	Unit	Quantity
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	20.780
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	17.634
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45080615201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	27.600
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	34.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	33.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	9.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,677.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45080615201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	695.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	60.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	577.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	353.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	29.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	294.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	22.806
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	10.392
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	8.817
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	38.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	3.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	16.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000

Call Order: 018 Proposal: T3964

ALT	Item	Description	Unit	Quantity
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	1.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	3.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000