

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                        |                                        |                            |                 |             |
|------------------------|----------------------------------------|----------------------------|-----------------|-------------|
| Letting:               | CT260325                               | Call Order: 001            | Proposal: T1920 | District:01 |
| Counties:              | MANATEE                                |                            |                 |             |
| Road Name:             | SR 684                                 |                            |                 |             |
| Limits:                | FROM SR 789 (GULF DR) TO W OF 123 ST W |                            |                 |             |
| Project(s):            | 43020425201(*)                         | Federal Aid No:            | D125024B        |             |
| Project(s):            | 43020425601                            | Federal Aid No:            | N/A             |             |
| Total Roadway Length:  | 0.311 Miles                            | Contract Days:             | 1200            |             |
| Total Bridge Length:   | 0.555 Miles                            | Letting Date:              | 03/25/26        |             |
| Total Proposal Length: | 0.866 Miles                            | Contract Execution Days:   | 10              |             |
|                        |                                        | Special Start Date:        | N/A             |             |
|                        |                                        | Aquis/Flexible Start Time: | 15 Days         |             |

Proposal Budget Estimate: \$129,946,504.00

Please read the full advertisement

**Description:**

This work under this project consists of bridge replacement, roadway reconstruction, milling and resurfacing, drainage, signalization, ITS, lighting, utility work and signing and pavement markings on SR 684 from SR 789 (Gulf Drive) to West of 123rd Street W in Manatee County.

**MANDATORY PRE-BID MEETING**

THERE WILL BE A MANDATORY PRE-BID MEETING FOR THIS PROJECT AT 9:00 AM EST ON WEDNESDAY, FEBRUARY 4, 2026, AT THE FLORIDA DEPARTMENT OF TRANSPORTATION, MANATEE OPERATIONS CENTER, 14000 SR 64 E, BRADENTON, FL 34212. IF YOU HAVE ANY QUESTIONS CONCERNING THIS MATTER, PLEASE CONTACT DON NAYLOR AT (863) 519-2629. AN ON-SITE VISIT WILL FOLLOW THE MEETING.

THIS PRE-BID MEETING IS MANDATORY BECAUSE OF THE COMPLEXITY OF THE PROJECT. ONLY PLANS AND SPECIFICATIONS WILL BE AVAILABLE PRIOR TO THE PRE-BID MEETING. THE PROSPECTIVE BIDDER SHALL BE PREQUALIFIED ACCORDING TO THE REQUIREMENTS OF FDOT RULE CHAPTER 14-22 AND SECTION 2-1 OF THE 2023 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

PROPOSALS (BIDDING DOCUMENTS) WILL BE ISSUED ONLY TO THE PROSPECTIVE BIDDERS WHO HAVE ATTENDED THE PRE-BID MEETING AND MET THE FLORIDA DEPARTMENT OF TRANSPORTATION QUALIFICATIONS FOR THIS PROJECT.

PROSPECTIVE BIDDERS ORDERING BID DOCUMENTS PRIOR TO THE PRE-BID MEETING WILL BE GIVEN ACCESS TO DOWNLOAD THE BID DOCUMENTS WITHIN 24 HOURS AFTER THE PRE-BID MEETING. THOSE PROSPECTIVE BIDDERS ORDERING THE DOCUMENTS AFTER THE PRE-BID MEETING WILL NEED TO CONTACT THE OFFICE ADVERTISING THE PROJECT TO CONFIRM ATTENDANCE AND RECEIVE ACCESS TO DOWNLOAD THE BID DOCUMENTS. PLEASE CONTACT THE OFFICE AT LEAST TWO WORKING DAYS PRIOR TO THE DEADLINE FOR OBTAINING BID DOCUMENTS TO ALLOW TIME FOR PROCESSING.

**Call Order: 001 Proposal: T1920**

| ALT                            | Item        | Description                                                                          | Unit | Quantity  |
|--------------------------------|-------------|--------------------------------------------------------------------------------------|------|-----------|
| <b>Section 0001 Structures</b> |             |                                                                                      |      |           |
|                                | 0103- 1- 26 | TEMPORARY WORK STRUCTURE, PROJECT NUMBER 430204-2-52-01 (43020425201 Br. No. 130168) | LS   | 1.000     |
|                                | 0110- 3-    | REMOVAL OF EXISTING STRUCTURES/BRIDGES (43020425201 Br. No. 130168)                  | LS   | 1.000     |
|                                | 0400- 0- 11 | CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011                                        | CY   | 41.300    |
|                                | 0400- 1- 30 | CONCRETE, CLASS I (SEAL)                                                             | CY   | 991.900   |
|                                | 0400- 2- 10 | CONCRETE CLASS II, APPROACH SLABS                                                    | CY   | 166.600   |
|                                | 0400- 4- 4  | CONCRETE CLASS IV, SUPERSTRUCTURE                                                    | CY   | 6,006.800 |

**Call Order: 001 Proposal: T1920**

| ALT | Item         | Description                                                                            | Unit | Quantity      |
|-----|--------------|----------------------------------------------------------------------------------------|------|---------------|
|     | 0400- 4- 5   | CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE                                                 | CY   | 225.600       |
|     | 0400- 4- 8   | CONC CLASS IV, BULKHEAD                                                                | CY   | 148.800       |
|     | 0400- 4- 11  | CONC CLASS IV, RETAINING WALLS                                                         | CY   | 239.700       |
|     | 0400- 4- 25  | CONCRETE CLASS IV, MASS, SUBSTRUCTURE                                                  | CY   | 10,023.000    |
|     | 0400- 7- 1   | BRIDGE DECK GROOVING                                                                   | SY   | 14,515.000    |
|     | 0400- 9- 1   | BRIDGE DECK PLANING                                                                    | SY   | 14,515.000    |
|     | 0400-147-    | COMPOSITE NEOPRENE PADS                                                                | CF   | 131.400       |
|     | 0415- 1- 3   | REINFORCING STEEL- RETAINING WALL                                                      | LB   | 32,656.000    |
|     | 0415- 1- 4   | REINFORCING STEEL - BRIDGE SUPERSTRUCTURE                                              | LB   | 1,140,271.000 |
|     | 0415- 1- 5   | REINFORCING STEEL- BRIDGE SUBSTRUCTURE                                                 | LB   | 3,129,841.000 |
|     | 0415- 1- 8   | REINFORCING STEEL- BULKHEAD                                                            | LB   | 2,003.000     |
|     | 0415- 1- 9   | REINFORCING STEEL- APPROACH SLABS                                                      | LB   | 32,692.000    |
|     | 0415- 10- 5  | FIBER REINFORCED POLYMER BARS, #5 BAR                                                  | LF   | 7,974.000     |
|     | 0450- 2- 36  | PREST BEAMS: FLORIDA-I BEAM 36"                                                        | LF   | 1,555.000     |
|     | 0450- 2- 63  | PREST BEAMS: FLORIDA-I BEAM 63"                                                        | LF   | 1,234.000     |
|     | 0450- 2- 84  | PREST BEAMS: FLORIDA-I BEAM 84"                                                        | LF   | 15,971.000    |
|     | 0455- 15- 16 | PREFORMED PILE HOLES, 36" TO 43" DRILL/PUNCH SIZE                                      | LF   | 17,274.000    |
|     | 0455- 20- 1  | PILE INSPECTION, DRIVEN PILE                                                           | EA   | 334.000       |
|     | 0455- 34- 6  | PRESTRESSED CONCRETE PILING, 30" SQ                                                    | LF   | 31,919.000    |
|     | 0455-115-    | PILE REDRIVE                                                                           | EA   | 188.000       |
|     | 0455-133- 2  | SHEET PILING STEEL, TEMPORARY-CRITICAL                                                 | SF   | 12,773.000    |
|     | 0455-133- 3  | SHEET PILING STEEL, F&I PERMANENT                                                      | SF   | 20,783.000    |
|     | 0455-133-208 | SOLDIER PILE WALL, PERMANENT, WITH CAST-IN-PLACE CONCRETE FASCIA                       | SF   | 1,369.000     |
|     | 0455-137-    | LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS                                      | EA   | 522.000       |
|     | 0455-137- 2  | LOAD TEST (DYNAMIC), VERIFICATION TEST                                                 | EA   | 20.000        |
|     | 0455-143- 6  | TEST PILES-PRESTRESSED CONCRETE,30" SQ                                                 | LF   | 2,280.000     |
|     | 0458- 1- 11  | BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD        | LF   | 280.000       |
|     | 0458- 1- 12  | BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL                          | LF   | 395.000       |
|     | 0459- 71-    | PILES, POLYETHYLENE SHEETING                                                           | SY   | 158.000       |
|     | 0465- 20-    | MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (43020425201 Br. No. 130168) | LS   | 1.000         |
|     | 0465- 21-    | MOVABLE BRIDGE OPERATOR                                                                | DA   | 638.000       |
|     | 0471- 3- 2   | POLYMERIC FENDER SYSTEM, 41-200 KIP-FT (43020425201 Br. No. 130168)                    | LS   | 1.000         |
|     | 0510- 1-     | NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (43020425201 Br. No. 130168)                   | LS   | 1.000         |
|     | 0515- 2-720  | PEDESTRIAN / BICYCLE RAILING, ALUMINUM, CUSTOM INFILL PANELS                           | LF   | 8,195.000     |
|     | 0521- 5- 13  | CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE                                     | LF   | 5,985.000     |
|     | 0521- 6- 34  | CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, CURB                       | LF   | 1,457.000     |
|     | 0524- 2- 2   | CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"                                            | SY   | 49.000        |
|     | 0530- 3- 3   | RIPRAP- RUBBLE, BANK AND SHORE                                                         | TN   | 1,360.100     |
|     | 0530- 5- 12  | GABION, MATTRESS 1 FOOT AND GREATER THICKNESS                                          | SY   | 219.000       |

**Call Order: 001 Proposal: T1920**

| ALT                         | Item         | Description                                                                     | Unit | Quantity    |
|-----------------------------|--------------|---------------------------------------------------------------------------------|------|-------------|
|                             | 0530- 74-    | BEDDING STONE                                                                   | TN   | 361.200     |
|                             | 0548- 12-    | RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER                             | SF   | 19,440.000  |
|                             | 0548- 13-    | RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER                             | SF   | 4,653.000   |
|                             | 0630- 2- 16  | CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS     | LF   | 20,944.000  |
|                             | 0635- 3- 13  | JUNCTION BOX, FURNISH & INSTALL, EMBEDDED                                       | EA   | 121.000     |
| <b>Section 0002 Roadway</b> |              |                                                                                 |      |             |
|                             | 0101- 1-     | MOBILIZATION (43020425201)                                                      | LS   | 1.000       |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (43020425201)                                            | LS   | 1.000       |
|                             | 0102- 2-200  | SPECIAL DETOUR- TEMPORARY PAVEMENT (43020425201)                                | LS   | 1.000       |
|                             | 0102- 2-300  | SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43020425201)                          | LS   | 1.000       |
|                             | 0102- 3-     | COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE                          | CY   | 6.400       |
|                             | 0102- 4- 1   | PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43020425201)                              | LS   | 1.000       |
|                             | 0102- 14-    | TRAFFIC CONTROL OFFICER                                                         | HR   | 160.000     |
|                             | 0102- 60-    | WORK ZONE SIGN                                                                  | ED   | 140,310.000 |
|                             | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE                                   | LF   | 1,874.000   |
|                             | 0102- 71- 15 | TEMPORARY BARRIER, F&I, ANCHORED                                                | LF   | 4,582.000   |
|                             | 0102- 71- 16 | TEMPORARY BARRIER, F&I, FREE STANDING                                           | LF   | 320.000     |
|                             | 0102- 71- 23 | TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE                               | LF   | 452.000     |
|                             | 0102- 71- 25 | TEMPORARY BARRIER, RELOCATE, ANCHORED                                           | LF   | 333.000     |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                          | ED   | 113,952.000 |
|                             | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)          | FD   | 446,976.000 |
|                             | 0102- 75- 1  | TEMPORARY SEPARATOR, F&I REMOVE                                                 | LF   | 296.000     |
|                             | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL                                       | ED   | 384.000     |
|                             | 0102- 89- 1  | TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION                                     | LO   | 7.000       |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                                     | ED   | 6,270.000   |
|                             | 0102-104-    | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                           | ED   | 1,200.000   |
|                             | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION                       | ED   | 1,200.000   |
|                             | 0102-115-    | TYPE III BARRICADE                                                              | ED   | 13,760.000  |
|                             | 0104- 10- 3  | SEDIMENT BARRIER                                                                | LF   | 5,358.000   |
|                             | 0104- 11-    | FLOATING TURBIDITY BARRIER                                                      | LF   | 626.000     |
|                             | 0104- 15-    | SOIL TRACKING PREVENTION DEVICE                                                 | EA   | 2.000       |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM                                                         | EA   | 10.000      |
|                             | 0107- 1-     | LITTER REMOVAL                                                                  | AC   | 252.640     |
|                             | 0107- 2-     | MOWING                                                                          | AC   | 167.720     |
|                             | 0108- 1-     | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43020425201) | LS   | 1.000       |
|                             | 0108- 2-     | MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43020425201)                 | LS   | 1.000       |
|                             | 0110- 1- 1   | CLEARING & GRUBBING (43020425201)                                               | LS   | 1.000       |
|                             | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE                                                    | SY   | 2,919.000   |
|                             | 0110- 86-    | DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43020425201)                          | LS   | 1.000       |
|                             | 0120- 1-     | REGULAR EXCAVATION                                                              | CY   | 19,386.000  |
|                             | 0120- 6-     | EMBANKMENT                                                                      | CY   | 22,176.000  |

**Call Order: 001 Proposal: T1920**

| ALT | Item         | Description                                                                     | Unit | Quantity  |
|-----|--------------|---------------------------------------------------------------------------------|------|-----------|
|     | 0160- 4-     | TYPE B STABILIZATION                                                            | SY   | 9,965.000 |
|     | 0285-706-    | OPTIONAL BASE, BASE GROUP 06                                                    | SY   | 9,079.000 |
|     | 0327- 70- 1  | MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH                                 | SY   | 183.000   |
|     | 0327- 70- 5  | MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH                                 | SY   | 4,279.000 |
|     | 0334- 1- 12  | SUPERPAVE ASPHALTIC CONC, TRAFFIC B                                             | TN   | 978.700   |
|     | 0337- 7- 81  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22                  | TN   | 1,102.600 |
|     | 0339- 1-     | MISCELLANEOUS ASPHALT PAVEMENT                                                  | TN   | 257.200   |
|     | 0425- 1-201  | INLETS, CURB, TYPE 9, <10'                                                      | EA   | 1.000     |
|     | 0425- 1-351  | INLETS, CURB, TYPE P-5, <10'                                                    | EA   | 8.000     |
|     | 0425- 1-451  | INLETS, CURB, TYPE J-5, <10'                                                    | EA   | 3.000     |
|     | 0425- 1-521  | INLETS, DT BOT, TYPE C, <10'                                                    | EA   | 2.000     |
|     | 0425- 1-531  | INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'                   | EA   | 1.000     |
|     | 0425- 1-549  | INLETS, DT BOT, TYPE D, MODIFY                                                  | EA   | 2.000     |
|     | 0425- 1-559  | INLETS, DT BOT, TYPE E, MODIFY                                                  | EA   | 2.000     |
|     | 0425- 1-589  | INLETS, DT BOT, TYPE H, MODIFY                                                  | EA   | 2.000     |
|     | 0425- 1-711  | INLETS, GUTTER, TYPE V, <10'                                                    | EA   | 1.000     |
|     | 0425- 1-715  | INLETS, GUTTER, TYPE V, PARTIAL                                                 | EA   | 1.000     |
|     | 0425- 1-923  | INLETS, ADJACENT BARRIER, J BOTTOM, < 10'                                       | EA   | 14.000    |
|     | 0425- 1-924  | INLETS, ADJACENT BARRIER, J BOTTOM, >10'                                        | EA   | 1.000     |
|     | 0425- 2- 41  | MANHOLES, P-7, <10'                                                             | EA   | 7.000     |
|     | 0425- 2- 43  | MANHOLES, P-7, PARTIAL                                                          | EA   | 3.000     |
|     | 0425- 2- 71  | MANHOLES, J-7, <10'                                                             | EA   | 11.000    |
|     | 0425- 2- 92  | MANHOLES, J-8, >10'                                                             | EA   | 1.000     |
|     | 0430-175-115 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD                                 | LF   | 38.000    |
|     | 0430-175-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD                                 | LF   | 1,453.000 |
|     | 0430-175-124 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD                                 | LF   | 342.000   |
|     | 0430-175-130 | PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD                                      | LF   | 928.000   |
|     | 0430-175-218 | PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD                       | LF   | 388.000   |
|     | 0430-175-224 | PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE-ELIP/ARCH, 24"S/CD                 | LF   | 17.000    |
|     | 0430-175-230 | PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD                    | LF   | 221.000   |
|     | 0430-185-142 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, JACK & BORE, 42", STORM AND CROSS DRAIN | LF   | 53.000    |
|     | 0430-982-125 | MITERED END SECTION, OPTIONAL ROUND, 18" CD                                     | EA   | 4.000     |
|     | 0430-982-133 | MITERED END SECTION, OPTIONAL ROUND, 30" CD                                     | EA   | 1.000     |
|     | 0430-982-629 | MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD                       | EA   | 1.000     |
|     | 0515- 1- 2   | PIPE HANDRAIL - GUIDERAIL, ALUMINUM                                             | LF   | 9.000     |
|     | 0515- 2-720  | PEDESTRIAN / BICYCLE RAILING, ALUMINUM, CUSTOM INFILL PANELS                    | LF   | 42.000    |
|     | 0519- 78-    | BOLLARDS                                                                        | EA   | 6.000     |
|     | 0520- 1- 7   | CONCRETE CURB & GUTTER, TYPE E                                                  | LF   | 501.000   |
|     | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F                                                  | LF   | 2,767.000 |
|     | 0520- 3-     | VALLEY GUTTER- CONCRETE                                                         | LF   | 166.000   |
|     | 0521- 72- 40 | SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT                                    | LF   | 864.000   |

**Call Order: 001 Proposal: T1920**

| ALT                         | Item         | Description                                                                                    | Unit | Quantity   |
|-----------------------------|--------------|------------------------------------------------------------------------------------------------|------|------------|
|                             | 0521- 72- 43 | SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER                                             | LF   | 59.000     |
|                             | 0522- 1-     | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK                                                      | SY   | 1,681.000  |
|                             | 0522- 2-     | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK                                                      | SY   | 3,013.000  |
|                             | 0524- 1- 1   | CONCRETE DITCH PAVT, NON REINFORCED, 3"                                                        | SY   | 49.000     |
|                             | 0527- 2-     | DETECTABLE WARNINGS                                                                            | SF   | 341.000    |
|                             | 0536- 1- 0   | GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2                                                     | LF   | 592.000    |
|                             | 0536- 8-111  | GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-<br>INDEX 536-001, APPROACH TL-2         | EA   | 2.000      |
|                             | 0536- 8-113  | GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-<br>INDEX 536-001, TRAILING              | EA   | 2.000      |
|                             | 0536- 73-    | GUARDRAIL REMOVAL                                                                              | LF   | 619.000    |
|                             | 0536- 85- 20 | GUARDRAIL END TREATMENT- TRAILING ANCHORAGE                                                    | EA   | 5.000      |
|                             | 0536- 85- 24 | GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL                                            | EA   | 5.000      |
|                             | 0570- 1- 2   | PERFORMANCE TURF, SOD                                                                          | SY   | 14,086.000 |
|                             | 0570- 1- 3   | PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT<br>INDEX 570-010                            | SY   | 68.000     |
|                             | 0571- 1- 11  | PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1                                               | SY   | 376.000    |
|                             | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH                                                        | LF   | 621.000    |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                                                 | EA   | 6,222.000  |
|                             | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                          | GM   | 6.329      |
|                             | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR<br>CROSSWALK AND ROUNDABOUT, 12"         | LF   | 1,590.000  |
|                             | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR<br>STOP LINE OR CROSSWALK, 24"           | LF   | 580.000    |
|                             | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED<br>GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 0.230      |
|                             | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR<br>SYMBOL                               | EA   | 12.000     |
|                             | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS                                             | EA   | 44.000     |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                                         | GM   | 6.529      |
|                             | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR<br>DIAGONAL OR CHEVRON, 18"             | LF   | 399.000    |
|                             | 0710- 11-231 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"                                          | GM   | 0.362      |
|                             | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4<br>DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM   | 0.308      |
|                             | 0999- 16-    | PARTNERING, DO NOT BID (43020425201)                                                           | LS   | 1.000      |
|                             | 0999- 20- 1  | DISPUTES REVIEW BOARD, MEETING- DO NOT BID                                                     | DA   | 40.000     |
|                             | 0999- 20- 2  | DISPUTES REVIEW BOARD, HEARING- DO NOT BID                                                     | EA   | 2.000      |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43020425201)                                           | LS   | 1.000      |
| <b>Section 0003 Signing</b> |              |                                                                                                |      |            |
|                             | 0700- 1-111  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT,<br>LESS THAN 12 SF                       | EA   | 47.000     |
|                             | 0700- 1-112  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT,<br>12.0-20.0 SF                          | EA   | 1.000      |
|                             | 0700- 1-211  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-<br>MOUNT, LESS THAN 12 SF                 | EA   | 3.000      |
|                             | 0700- 1-212  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-<br>MOUNT, 12.0-20.0 SF                    | EA   | 1.000      |
|                             | 0700- 1-500  | SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE                                                   | EA   | 7.000      |

**Call Order: 001 Proposal: T1920**

| ALT                          | Item         | Description                                                                                    | Unit | Quantity  |
|------------------------------|--------------|------------------------------------------------------------------------------------------------|------|-----------|
|                              | 0700- 1-600  | SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE                                                     | EA   | 45.000    |
|                              | 0700- 1-912  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER<br>GROUND MOUNT, 12.0-20.0 SF               | EA   | 1.000     |
|                              | 0700- 2-600  | MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE                                                      | EA   | 1.000     |
|                              | 0700- 3-602  | SIGN PANEL, REMOVE, 12-20 SF                                                                   | EA   | 2.000     |
|                              | 0704- 1- 3   | TUBULAR MARKER, 36" WHITE POST                                                                 | EA   | 2.000     |
|                              | 0705- 10- 1  | OBJECT MARKER, TYPE 1                                                                          | EA   | 8.000     |
|                              | 0705- 10- 4  | OBJECT MARKER, TYPE 4                                                                          | EA   | 3.000     |
|                              | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                                                 | EA   | 500.000   |
|                              | 0710- 12-290 | PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND<br>NOSE                               | SF   | 28.000    |
|                              | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43020425201)                                         | LS   | 1.000     |
|                              | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR<br>INTERCHANGE AND URBAN ISLAND                  | GM   | 0.047     |
|                              | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK<br>AND ROUNDABOUT                     | LF   | 894.000   |
|                              | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE<br>AND CROSSWALK                      | LF   | 193.000   |
|                              | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10<br>GAP EXTENSION, 6"                | GM   | 0.166     |
|                              | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL                                              | EA   | 5.000     |
|                              | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW                                                          | EA   | 19.000    |
|                              | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL<br>OR CHEVRON                         | LF   | 294.000   |
|                              | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-<br>10 DOTTED EXTENSION LINE, 6"     | GM   | 0.051     |
|                              | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR<br>CROSSWALK                                   | LF   | 254.000   |
|                              | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE                                                       | EA   | 11.000    |
|                              | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW                                                         | EA   | 11.000    |
|                              | 0711- 14-560 | THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON<br>CONCRETE PAVEMENT, MESSAGE OR SYMBOL | EA   | 6.000     |
|                              | 0711- 14-570 | THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST,<br>ARROW ON CONCRETE SURFACE              | EA   | 6.000     |
|                              | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                                       | GM   | 1.240     |
|                              | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP,<br>6",10-30 SKIP OR 3-9 LANE DROP         | GM   | 0.026     |
|                              | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID,<br>6"                                   | GM   | 1.030     |
|                              | 0711- 16-231 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"                                       | GM   | 0.207     |
|                              | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES                                          | GM   | 2.221     |
|                              | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES                                         | GM   | 1.203     |
| <b>Section 0004 Lighting</b> |              |                                                                                                |      |           |
|                              | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH                                                        | LF   | 4,887.000 |
|                              | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE                                                   | LF   | 466.000   |
|                              | 0630- 2- 16  | CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS<br>AND TRAFFIC RAILINGS                 | LF   | 1,116.000 |
|                              | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE                                                   | EA   | 48.000    |
|                              | 0635- 3- 13  | JUNCTION BOX, FURNISH & INSTALL, EMBEDDED                                                      | EA   | 16.000    |

**Call Order: 001 Proposal: T1920**

| ALT                               | Item         | Description                                                                                                             | Unit | Quantity   |
|-----------------------------------|--------------|-------------------------------------------------------------------------------------------------------------------------|------|------------|
|                                   | 0639- 1-122  | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR                                               | AS   | 4.000      |
|                                   | 0639- 2- 1   | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL                                                                              | LF   | 271.000    |
|                                   | 0639- 3- 11  | ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT                                                                          | EA   | 4.000      |
|                                   | 0641- 2- 12  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE                                                                  | EA   | 4.000      |
|                                   | 0715- 1- 11  | LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <                                                                        | LF   | 9,028.000  |
|                                   | 0715- 1- 12  | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6                                                                           | LF   | 54,665.000 |
|                                   | 0715- 1- 13  | LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2                                                                       | LF   | 14,659.000 |
|                                   | 0715- 1- 60  | LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS                                                                  | LF   | 9,351.000  |
|                                   | 0715- 7- 11  | LOAD CENTER, F&I, SECONDARY VOLTAGE                                                                                     | EA   | 4.000      |
|                                   | 0715- 7- 41  | LOAD CENTER, REMOVE, SECONDARY VOLTAGE                                                                                  | EA   | 4.000      |
|                                   | 0715- 11-125 | LUMINAIRE, F&I, UNDER DECK, WALL MOUNT                                                                                  | EA   | 7.000      |
|                                   | 0715- 11-128 | LUMINAIRE, F&I, UNDER DECK, FLOOD                                                                                       | EA   | 34.000     |
|                                   | 0715- 11-211 | LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD                                    | EA   | 2.000      |
|                                   | 0715- 61-100 | LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 0' ARM LENGTH                         | EA   | 1.000      |
|                                   | 0715- 61-252 | LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 15' ARM LENGTH                        | EA   | 1.000      |
|                                   | 0715- 61-811 | LIGHT POLE COMPLETE, F&I, STD POLE STD FOUNDATION, WILDLIFE SENSITIVE LUMINAIRE, 25' MOUNTING HEIGHT, 8' ARM LENGTH     | EA   | 1.000      |
|                                   | 0715- 62-252 | LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT, 15' ARM LENGTH                         | EA   | 2.000      |
|                                   | 0715- 62-811 | LIGHT POLE COMPLETE, F&I, STD POLE SPECIAL FOUNDATION, WILDLIFE SENSITIVE LUMINAIRE, 25' MOUNTING HEIGHT, 8' ARM LENGTH | EA   | 2.000      |
|                                   | 0715- 65-266 | LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH                | EA   | 1.000      |
|                                   | 0715- 66-266 | LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH                 | EA   | 1.000      |
|                                   | 0715- 69-000 | LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION                                                                         | EA   | 21.000     |
|                                   | 0715-500- 1  | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL                                                       | EA   | 25.000     |
|                                   | 0715-500- 3  | POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT                                                                              | EA   | 84.000     |
|                                   | 0715-516-125 | LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MOUNT- ALUMINUM, 25'                                                 | EA   | 90.000     |
|                                   | 0715-516-130 | LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, POLE TOP MOUNT- ALUMINUM, 30'                                                 | EA   | 8.000      |
| <b>Section 0005 Signalization</b> |              |                                                                                                                         |      |            |
|                                   | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH                                                                                 | LF   | 45.000     |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE                                                                            | LF   | 60.000     |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                                                      | PI   | 1.000      |
|                                   | 0632- 7- 6   | SIGNAL CABLE, REMOVE- INTERSECTION                                                                                      | PI   | 1.000      |
|                                   | 0635- 2- 14  | PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE                                                                            | EA   | 4.000      |
|                                   | 0646- 1- 11  | ALUMINUM SIGNALS POLE, PEDESTAL                                                                                         | EA   | 3.000      |
|                                   | 0646- 1- 60  | ALUMINUM SIGNALS POLE, REMOVE                                                                                           | EA   | 2.000      |

**Call Order: 001 Proposal: T1920**

| ALT                           | Item         | Description                                                                                                           | Unit | Quantity  |
|-------------------------------|--------------|-----------------------------------------------------------------------------------------------------------------------|------|-----------|
|                               | 0650- 1- 14  | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY                                                | AS   | 1.000     |
|                               | 0650- 1- 19  | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY                                        | AS   | 1.000     |
|                               | 0650- 1- 60  | VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN                                                                     | AS   | 2.000     |
|                               | 0653- 1- 11  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY                                                             | AS   | 3.000     |
|                               | 0654- 2- 22  | MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK | AS   | 2.000     |
|                               | 0660- 1-600  | LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN                                                                    | EA   | 5.000     |
|                               | 0660- 3- 11  | VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT                                              | EA   | 1.000     |
|                               | 0660- 3- 12  | VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT                                        | EA   | 3.000     |
|                               | 0665- 1- 12  | PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE                                                                    | EA   | 3.000     |
|                               | 0671- 2- 40  | TRAFFIC CONTROLLER, MODIFY                                                                                            | EA   | 1.000     |
|                               | 0676- 1-500  | TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY                                                                      | EA   | 1.000     |
|                               | 0700- 3-201  | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF                                                             | EA   | 3.000     |
|                               | 0700- 3-601  | SIGN PANEL, REMOVE, UP TO 12 SF                                                                                       | EA   | 3.000     |
|                               | 0700-141-903 | ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - OVERHEAD MOUNT                                                   | EA   | 1.000     |
| <b>Section 0006 Utilities</b> |              |                                                                                                                       |      |           |
|                               | 0425- 2-110  | MANHOLES, REPAIR                                                                                                      | EA   | 1.000     |
|                               | 0425- 5- 1   | MANHOLE, ADJUST, UTILITIES                                                                                            | EA   | 2.000     |
|                               | 0425- 6-     | VALVE BOXES, ADJUST                                                                                                   | EA   | 4.000     |
|                               | 0430-830-    | PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE                                                                       | CY   | 2.000     |
|                               | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43020425601)                                                                  | LS   | 1.000     |
|                               | 1050- 16-001 | UTILITY PIPE,REMOVE & DISPOSE, 0 - 1.9"                                                                               | LF   | 15.000    |
|                               | 1050- 16-002 | UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"                                                                                 | LF   | 20.000    |
|                               | 1050- 16-003 | UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"                                                                                 | LF   | 1,053.000 |
|                               | 1050- 16-004 | UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"                                                                                | LF   | 1,685.000 |
|                               | 1050- 16-005 | UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"                                                                               | LF   | 4,284.000 |
|                               | 1050- 17-005 | UTILITY PIPE,REMOVE & STOCKPILE/SALVAGE, 20-49.9"                                                                     | LF   | 65.000    |
|                               | 1050- 31-206 | UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"                                                 | LF   | 552.000   |
|                               | 1050- 31-220 | UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 20"                                                | LF   | 43.000    |
|                               | 1050- 42-208 | UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 8"                                           | LF   | 287.000   |
|                               | 1050- 51-204 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 4"                                              | LF   | 20.000    |
|                               | 1050- 51-206 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 6"                                              | LF   | 63.000    |
|                               | 1050- 51-216 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 16"                                             | LF   | 45.000    |
|                               | 1050- 51-220 | UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 20"                                             | LF   | 90.000    |
|                               | 1050- 61-112 | UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 12"                                                                   | LF   | 23.000    |

**Call Order: 001 Proposal: T1920**

| ALT                                                   | Item         | Description                                                                | Unit | Quantity  |
|-------------------------------------------------------|--------------|----------------------------------------------------------------------------|------|-----------|
|                                                       | 1055- 13-    | UTILITY FITTINGS, INSTALL                                                  | EA   | 6.000     |
|                                                       | 1055- 31-108 | UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 8"              | EA   | 2.000     |
|                                                       | 1055- 31-120 | UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 20"             | EA   | 4.000     |
|                                                       | 1055- 31-308 | UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, REDUCER, 8"            | EA   | 2.000     |
|                                                       | 1055- 51-116 | UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 16"     | EA   | 3.000     |
|                                                       | 1055- 51-120 | UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 20"     | EA   | 4.000     |
|                                                       | 1055- 51-616 | UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL Y, 16"         | EA   | 1.000     |
|                                                       | 1060- 11-211 | UTILITY STRUCTURE, BELOW GROUND, F&I, WATER/SEWER, 0 - 80 FT3, 0 - 6'      | EA   | 1.000     |
|                                                       | 1060- 15-    | UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY                             | EA   | 2.000     |
|                                                       | 1060- 16-    | UTILITY STRUCTURE, BELOW GROUND, REMOVE&DISPOSE CONTRACTOR TAKES OWNERSHIP | EA   | 3.000     |
|                                                       | 1080- 21-600 | UTILITY FIXTURE, VALVE/METER BOX, REMOVE                                   | EA   | 1.000     |
|                                                       | 1080- 24-106 | UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"                   | EA   | 2.000     |
|                                                       | 1080- 24-600 | UTILITY FIXTURE, VALVE ASSEMBLY, REMOVE                                    | EA   | 22.000    |
|                                                       | 1080- 26-106 | UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 6"                    | EA   | 1.000     |
|                                                       | 1080- 26-600 | UTILITY FIXTURE, VAC/AIR ASSEMBLY, REMOVE                                  | EA   | 1.000     |
|                                                       | 1644-112- 06 | FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 6"                                    | EA   | 1.000     |
|                                                       | 1644-900-    | FIRE HYDRANT, REMOVE                                                       | EA   | 1.000     |
| <b>Section 0007 Intelligent Transportation System</b> |              |                                                                            |      |           |
|                                                       | 0611- 1- 1   | ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH                             | MI   | 0.900     |
|                                                       | 0611- 2- 1   | ITSFM LOCATION DOCUMENTATION- INTERSECTION                                 | EA   | 1.000     |
|                                                       | 0611- 2- 2   | ITSFM LOCATION DOCUMENTATION- ITS SITE                                     | EA   | 2.000     |
|                                                       | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH                                    | LF   | 998.000   |
|                                                       | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE                               | LF   | 528.000   |
|                                                       | 0630- 2- 14  | CONDUIT, FURNISH & INSTALL, ABOVEGROUND                                    | LF   | 10.000    |
|                                                       | 0633- 1-121  | FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS                            | LF   | 907.000   |
|                                                       | 0633- 1-123  | FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS                           | LF   | 4,898.000 |
|                                                       | 0633- 2- 31  | FIBER OPTIC CONNECTION, INSTALL, SPLICE                                    | EA   | 118.000   |
|                                                       | 0633- 3- 11  | FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE                     | EA   | 3.000     |
|                                                       | 0633- 3- 12  | FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY                          | EA   | 3.000     |
|                                                       | 0633- 3- 13  | FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY     | EA   | 3.000     |
|                                                       | 0633- 3- 16  | FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED        | EA   | 3.000     |
|                                                       | 0633- 6-     | FIBER OPTIC CABLE LOCATOR                                                  | DA   | 1,200.000 |
|                                                       | 0635- 2- 12  | PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE                               | EA   | 5.000     |
|                                                       | 0635- 2- 13  | PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE      | EA   | 3.000     |
|                                                       | 0635- 2- 14  | PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE                               | EA   | 2.000     |
|                                                       | 0639- 1-122  | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR  | AS   | 2.000     |
|                                                       | 0639- 1-620  | ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND                               | AS   | 1.000     |

**Call Order: 001 Proposal: T1920**

| ALT | Item         | Description                                                                            | Unit | Quantity |
|-----|--------------|----------------------------------------------------------------------------------------|------|----------|
|     | 0639- 2- 1   | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL                                             | LF   | 144.000  |
|     | 0639- 3- 11  | ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT                                         | EA   | 2.000    |
|     | 0641- 2- 12  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE                                 | EA   | 2.000    |
|     | 0641- 2- 80  | PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER                 | EA   | 1.000    |
|     | 0641- 3-263  | CONCRETE CCTV POLE, FURNISH & INSTALL WITHOUT LOWERING DEVICE, 63'                     | EA   | 2.000    |
|     | 0641- 3-800  | CONCRETE CCTV POLE, COMPLETE POLE REMOVAL                                              | EA   | 1.000    |
|     | 0660- 3- 11  | VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT               | EA   | 1.000    |
|     | 0660- 3- 12  | VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT         | EA   | 1.000    |
|     | 0660- 6-121  | VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT         | EA   | 1.000    |
|     | 0660- 6-122  | VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT    | EA   | 1.000    |
|     | 0660- 6-600  | VEHICLE DETECTION SYSTEM- AVI, REMOVE COMPLETE SYSTEM                                  | EA   | 2.000    |
|     | 0660- 11- 60 | TRAFFIC DATA DETECTION SYSTEM- LIDAR, REMOVE COMPLETE SYSTEM                           | EA   | 1.000    |
|     | 0676- 2-122  | ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D | EA   | 2.000    |
|     | 0676- 2-600  | ITS CABINET- REMOVE                                                                    | EA   | 1.000    |
|     | 0682- 1-163  | ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION                                      | EA   | 2.000    |
|     | 0682- 1-600  | ITS CCTV CAMERA, REMOVE & DISPOSAL                                                     | EA   | 1.000    |
|     | 0684- 1- 1   | MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL                                       | EA   | 2.000    |
|     | 0684- 2- 1   | DEVICE SERVER, FURNISH & INSTALL                                                       | EA   | 1.000    |
|     | 0684- 6- 6   | WIRELESS COMMUNICATION SYSTEM DEVICE, REMOVE                                           | EA   | 2.000    |
|     | 0685- 1- 11  | UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE                    | EA   | 2.000    |
|     | 0924-681- 1  | CONNECTED VEHICLE ROADSIDE EQUIPMENT, RSU                                              | EA   | 1.000    |