

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 010	Proposal: T3A23	District:03
Counties:	JACKSON			
Road Name:	SR 75 (US 231)			
Limits:	FROM S OF SR 10 (US 90) TO END OF CURB AND GUTTER			
Project(s):	45293315201(*)	Federal Aid No:	D326034B	
Project(s):	45293315202	Federal Aid No:	N/A	
Total Roadway Length:	1.399 Miles	Contract Days:	200	
Total Bridge Length:	0.000 Miles	Letting Date:	09/30/26	
Total Proposal Length:	1.399 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days Flexible	
Proposal Budget Estimate:	\$2,371,025.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of RRR SR 75 (US 231) S of SR 10 (US 90) to end of curb and gutter. The improvements include curb ramp reconstruction, replacement of strain poles for overhead school zone signage, signing and pavement marking upgrades, driveway reconstruction, and signal timing upgrades.

Call Order: 010 Proposal: T3A23

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45293315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45293315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	88.000
	0102- 60-	WORK ZONE SIGN	ED	15,772.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	37,424.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	720.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	2,474.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,256.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	200.000
	0104- 10- 3	SEDIMENT BARRIER	LF	746.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	60.000
	0107- 1-	LITTER REMOVAL	AC	49.050
	0107- 2-	MOWING	AC	31.210
	0110- 1- 1	CLEARING & GRUBBING (45293315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	588.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	135.400
	0160- 4-	TYPE B STABILIZATION	SY	751.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	174.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	361.000

Call Order: 010 Proposal: T3A23

ALT	Item	Description	Unit	Quantity
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	78.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	10,914.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	43,729.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	737.900
	0334- 1- 57	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, HIGH POLYMER	TN	477.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,609.800
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, HIGH POLYMER	TN	945.800
	0425- 5-	MANHOLE, ADJUST	EA	12.000
	0425- 6-	VALVE BOXES, ADJUST	EA	8.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	796.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	69.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	147.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	256.000
	0527- 2-	DETECTABLE WARNINGS	SF	424.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	828.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	20.700
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.482
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,689.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	94.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	980.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.868
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	70.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.282
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	204.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	3.070
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45293315201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	14.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	8.000
	0700-142-131	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,237.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45293315201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,689.000

Call Order: 010 Proposal: T3A23

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	94.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	980.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	70.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	204.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	686.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	43.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	545.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.741
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.434
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.641
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.535
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	33.000

Section 0003 Signalization

	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	60.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,575.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0634- 4-151	SPAN WIRE ASSEMBLY, F&I, TWO POINT, PERPENDICULAR	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	22.000
	0641- 2- 15	PRESTRESSED CONCRETE POLE, F&I, TYPE P-V	EA	4.000
	0649- 1- 65	STEEL STRAIN POLE, REMOVE, DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT	EA	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	16.000
	0660- 1-102	LOOP DETECTOR INDUCTIVE, F&I, TYPE 2	EA	4.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	7.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	7.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	2.000
	0700-141-314	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, W/BEACON, 31-50 SF OF STATIC SIGN PANELS	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000