

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260610 Call Order: 008 Proposal: T5885 District:05

Counties: VOLUSIA

Road Name: SR 400 (I-4)

Limits: FROM MP 21.540 TO MP 22.558

Project(s): 44644545201(*)

Federal Aid No: D525040B

Total Roadway Length:	1.018 Miles	Contract Days:	450
Total Bridge Length:	0.000 Miles	Letting Date:	06/10/26
Total Proposal Length:	1.018 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	0 Days

Proposal Budget Estimate: \$48,220,833.00

Please read the full advertisement

Description: Bonus

The Improvements under this Contract consist of constructing an approximately 54 acre Westbound Volusia County Truck Parking site and associated ramps along approximately 1 mile of I-4(SR 400) which includes Base Work, Shoulder Treatment, Drainage Improvements, Curb & Gutter, Lighting, Highway Signing, Guardrail, Landscaping, Sidewalks, ITS, an FPL Conduit Route, Concrete Pavement, Buildings, Wells, and a Septic System.

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44644545201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44644545201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44644545201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44644545201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,808.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	6,150.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	4,063.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	23,382.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	20.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	5.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	968.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	450.000
	0102-115-	TYPE III BARRICADE	ED	1,488.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	40.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	20.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	2.319
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.625
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	2.319
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.314
	0104- 10- 3	SEDIMENT BARRIER	LF	4,149.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	5,086.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	273.940

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	593.550
	0110- 1- 1	CLEARING & GRUBBING (44644545201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	2.190
	0110- 21-	TREE PROTECTION BARRIER	LF	10,756.000
	0120- 1-	REGULAR EXCAVATION	CY	95,671.000
	0120- 4-	SUBSOIL EXCAVATION	CY	77,876.100
	0120- 6-	EMBANKMENT	CY	437,752.400
	0160- 4-	TYPE B STABILIZATION	SY	116,288.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	4,406.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	2,872.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	58,508.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	691.900
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	8,033.900
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,421.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	343.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	55.800
	0350- 3- 9	PLAIN CEMENT CONCRETE PAVEMENT, 10"	SY	57.000
	0350- 3- 13	PLAIN CEMENT CONCRETE PAVEMENT, 12"	SY	4,349.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	7,402.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	5,161.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	9.000
	0425- 1-523	INLETS, DT BOT, TYPE C, JBOT, <10'	EA	1.000
	0425- 1-524	INLETS, DT BOT, TYPE C, JBOT, >10'	EA	1.000
	0425- 1-571	INLETS, DITCH BOTTOM, TYPE G, <10'	EA	30.000
	0425- 1-572	INLETS, DITCH BOTTOM, TYPE G, >10'	EA	1.000
	0425- 1-574	INLETS, DITCH BOTTOM, TYPE G, J BOT, >10'	EA	8.000
	0425- 1-705	INLETS, GUTTER, TYPE S, PARTIAL	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	3.000
	0425- 2- 42	MANHOLES, P-7, >10'	EA	6.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	1,992.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	1,304.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,142.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	439.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	391.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	293.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	2,871.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-964- 6	PVC PIPE, 8 INCH	LF	505.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	1.000

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	5.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	1.000
	0440- 1- 10	UNDERDRAIN, TYPE I	LF	74.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	3,151.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	224.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	7,634.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	33.000
	0520- 2- 10	CONCRETE CURB, TOLL HEADER CURB	LF	415.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	40.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	677.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	6,212.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	35.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	228.000
	0527- 2-	DETECTABLE WARNINGS	SF	312.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	45.000
	0530- 74-	BEDDING STONE	TN	33.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	588.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	125.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	125.000
	0536- 73-	GUARDRAIL REMOVAL	LF	369.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 29	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	1.000
	0550- 10-169	FENCING, TYPE A, 10.1-12.0', SPECIAL FEATURES	LF	7,394.000
	0550- 10-210	FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES	LF	466.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	1,743.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	403.000
	0550- 60-123	FENCE GATE, TYPE A, DOUBLE, 12.1-18.0' OPENING	EA	2.000
	0550- 60-211	FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING	EA	6.000
	0550- 60-223	FENCE GATE, TYPE B, DOUBLE, 12.1-18.0' OPENING	EA	2.000
	0550- 60-232	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 6.1-12' OPENING	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	24,565.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	164,113.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	966.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	11.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44644545201)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	1.292
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	45.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	15.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 7-231	EMBEDDED DYNAMIC MESSAGE SIGN, FURNISH & INSTALL-WITHOUT UPS, FULL COLOR, UP TO 12 SF	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	6.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	12.000
	0700-141-180	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/EDS AND HIGHLIGHTED SIGN <12 SF	EA	4.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	151.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,067.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	191.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44644545201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.322
	0711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6" FOR PARKING SPACES	LF	17,122.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	639.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,228.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	85.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.986
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	24.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	994.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	634.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.917
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.065
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.645
	0713-103-171	PERMANENT TAPE, WHITE, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.319
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	2.629
	0713-103-371	PERMANENT TAPE, BLACK, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.319
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	2.629
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	13,780.000

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	116.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	48,344.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	14,499.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 61-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	36.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	6.000
	0715- 61-811	LIGHT POLE COMPLETE, F&I, STD POLE STD FOUNDATION, WILDLIFE SENSITIVE LUMINAIRE, 25' MOUNTING HEIGHT, 8' ARM LENGTH	EA	16.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	86.000
	0715-511-130	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 30'	EA	4.000
	0715-511-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 35'	EA	3.000
	0715-511-145	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 45'	EA	4.000
	0715-511-150	LIGHT POLE COMPLETE SPECIAL DESIGN , F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 50'	EA	1.000
	0715-512-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 35'	EA	10.000
	0715-512-140	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 40'	EA	4.000
	0715-512-145	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 45'	EA	2.000
Section 0004 Architectural				
	0519- 78-	BOLLARDS	EA	5.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	11,510.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0635- 2-219	PULL BOX, HS-20, FURNISH & INSTALL, 24" X 36"	EA	46.000
	0635- 2-220	PULL BOX, HS-20, FURNISH & INSTALL, 13" X 24"	EA	27.000
	0635- 2-221	EV POWER CONDUIT VAULT, 11' X 21' X 9.5' (10' X 20' X 8')	EA	6.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	62.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (44644545201)	LS	1.000
	0750- 1- 11	ARCHITECTURAL, BUILDING, NEW, REST AREA (44644545201)	LS	1.000
	0750- 1- 17	ARCHITECTURAL, BUILDING, NEW, STORAGE/MECHANICAL (44644545201)	LS	1.000
	0751- 5-	ARCHITECTURAL-WATER, SANITARY SEWER/SEWAGE TREATMENT (44644545201)	LS	1.000
	0751- 30- 1	ARCHITECTURAL, PICNIC PAVILION, SMALL	EA	5.000
	0751- 37-	TRASH RECEPTACLE	EA	43.000

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
	0751- 37- 1	TRASH RECEPTACLE- ASH URN	EA	36.000
	0751- 37- 2	TRASH RECEPTACLE- DOG WASTE	EA	15.000
	0751- 38- 13	BENCH, F&I, CONCRETE	EA	7.000
	0751- 44- 2	FLAG POLE, 26-35'	EA	3.000
Section 0005 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.018
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	9.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	21,910.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,715.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	80.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	5,841.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	16,190.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	13,190.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	336.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	156.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	2.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	4.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	13.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	37.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	5.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	450.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	7,766.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	52.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	51.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-500	ELECTRICAL POWER SERVICE, ADJUST/MODIFY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	13,984.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	8,954.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	8.000
	0639- 6-141	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, 16-25 KVA, SINGLE PHASE, COPPER WINDINGS	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	9.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	1.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	1.000
	0660- 12- 11	VEHICLE DETECTION SYSTEM- TRUCK PARKING DETECTION SYSTEM, FURNISH & INSTALL, SENSOR- CAMERA	EA	28.000
	0660- 12- 14	VEHICLE DETECTION SYSTEM- TRUCK PARKING DETECTION SYSTEM, FURNISH & INSTALL, CENTRAL SOFTWARE	EA	1.000

Call Order: 008 Proposal: T5885

ALT	Item	Description	Unit	Quantity
	0676- 2-131	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 336, 24" W X 36" H X 20" D	EA	1.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	8.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	18.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	4.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	2.000
	0684- 7- 1	MANAGED HUB ETHERNET SWITCH, FURNISH & INSTALL	EA	9.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	9.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	9.000