

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 004	Proposal: T1949	District:01
Counties:	LEE			
Road Name:	SR 93 (I-75)			
Limits:	FROM N OF ALICO RD TO S OF DANIELS PKWY			
Project(s):	45279315201(*)	Federal Aid No:	D126066B	
Total Roadway Length:	5.197 Miles	Contract Days:	180	
Total Bridge Length:	0.073 Miles	Letting Date:	10/28/26	
Total Proposal Length:	5.270 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	

Proposal Budget Estimate: \$8,686,181.00

Please read the full advertisement

Description:

The Improvements under this contract consist of milling and resurfacing and signing and pavement markings on SR 93 (I-75) from North of Alico Road to South of Daniels Parkway in Lee County.

Call Order: 004 Proposal: T1949

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 28	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITHOUT BACKER ROD	LF	224.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	28.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45279315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45279315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,800.000
	0102- 60-	WORK ZONE SIGN	ED	13,812.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	31,950.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	270.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	2,616.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,468.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	180.000
	0102-115-	TYPE III BARRICADE	ED	180.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	360.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	72,143.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	495.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	76,400.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	171,638.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	19,972.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	6,887.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	18,766.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	2,998.500

Call Order: 004 Proposal: T1949

ALT	Item	Description	Unit	Quantity
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	41.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	202.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	8.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	9.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.239
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.009
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,222.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	13.694
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.981
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	5.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.495
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45279315201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	13.916
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	5.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	16.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	10.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	5.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	8.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	3.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	3.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	3.000
	0700- 3-611	SIGN PANEL, REMOVE, 601 SF AND GREATER	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,616.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45279315201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,222.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	5.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	27.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	3.000

Call Order: 004 Proposal: T1949

ALT	Item	Description	Unit	Quantity
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.239
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.009
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	13.694
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.981
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	7.495
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.046
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.091
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.046
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.091
Section 0004 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	180.000