Vendor Ranking

Letting: CT261028 October 28, 2026 10:30 AM **Call Order:** 012 **Contract:** T3970

District: District 3 **Counties:** GADSDEN **Fed Aid No:** D326018B

Contract Time: 310 AVAILABLE DAYS **Project(s):** 44118815201 (*)

Contract Desc: HANNA MILL POND RD OVER HANNA POND BRIDGE NO 504043

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	RBM CONTRACTING SERVICES, LLC	Responsive	Winning bid	$5,235,654.56	100.00%
2	SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC	Responsive	Non-Winning Bid	$5,266,922.25	100.60%
3	F & W CONSTRUCTION COMPANY, INC.	Responsive	Non-Winning Bid	$5,870,272.80	112.12%
4	MURPHREE BRIDGE CORPORATION	Responsive	Non-Winning Bid	$5,907,876.71	112.84%
5	ANDERSON COLUMBIA CO., INC.	Responsive	Non-Winning Bid	$6,040,768.40	115.38%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

District: District 3 **Counties:** GADSDEN **Fed Aid No:** D326018B

Contract Time: 310 AVAILABLE DAYS **Project(s):** 44118815201 (*)

Contract Descr: HANNA MILL POND RD OVER HANNA POND BRIDGE NO 504043

The improvements under this Contract consist of replacing the structurally deficient bridge culvert (Bridge No. 504043) on Hanna Mill Pond Road over Hanna Mill Pond with a new concrete bridge (Bridge No. 504160) within its existing alignment. The single barrel arched pipe culvert located approximately 200 feet` west, of the bridge culvert is also being replaced with a concrete box culvert and concrete barrier. Other roadway improvements are paved shoulders, drainage improvements, guardrail, concrete barrier, and signing and pavement markings. Additionally, the weir structures and splash pads at the bridge and pipe culverts are being replaced with concrete covered steel sheet pile wall, riprap, and seal concrete. A project detour will be in place in Gadsden County.

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (1488.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 44118815201	200,000.00000	200,000.00	300,000.00000	300,000.00	660,000.00000	660,000.00
0010 0400 1 30 65.400 CY CONCRETE, CLASS I (SEAL)	350.00000	22,890.00	710.00000	46,434.00	1,500.00000	98,100.00
0015 0400 2 4 92.800 CY CONC CLASS II, BRIDGE SUPERSTRUCTURE	1,500.00000	139,200.00	2,370.00000	219,936.00	1,800.00000	167,040.00
0020 0400 2 10 43.700 CY CONCRETE CLASS II, APPROACH SLABS	970.00000	42,389.00	870.00000	38,019.00	1,200.00000	52,440.00
0025 0400 4 5 72.800 CY CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	3,650.00000	265,720.00	4,305.00000	313,404.00	1,500.00000	109,200.00
0030 0400 4 8 158.800 CY CONC CLASS IV, BULKHEAD	2,235.00000	354,918.00	1,525.00000	242,170.00	1,600.00000	254,080.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0035 0400 7 1 BRIDGE DECK GROOVING 192.000 SY	22.00000	4,224.00	36.00000	6,912.00	52.00000	9,984.00
0040 0400148 PLAIN NEOPRENE BEARING PADS 2.600 CF	3,000.00000	7,800.00	3,670.00000	9,542.00	3,000.00000	7,800.00
0045 0415 1 4 REINFORCING STEEL - BRIDGE SUPERSTRUCTURE 27,719.000 LB	2.70000	74,841.30	1.50000	41,578.50	2.00000	55,438.00
0050 0415 1 5 REINFORCING STEEL- BRIDGE SUBSTRUCTURE 23,906.000 LB	2.70000	64,546.20	1.50000	35,859.00	2.00000	47,812.00
0055 0415 1 8 REINFORCING STEEL- BULKHEAD 7,233.000 LB	3.50000	25,315.50	3.75000	27,123.75	2.00000	14,466.00
0060 0415 1 9 REINFORCING STEEL- APPROACH SLABS 8,580.000 LB	3.50000	30,030.00	1.50000	12,870.00	2.00000	17,160.00
0065 0455 20 1 PILE INSPECTION, DRIVEN PILE 16.000 EA	910.00000	14,560.00	525.00000	8,400.00	5,000.00000	80,000.00
0070 0455 34 3 PRESTRESSED CONCRETE PILING, 18" SQ 684.000 LF	155.00000	106,020.00	220.00000	150,480.00	85.00000	58,140.00
0075 0455115 PILE REDRIVE 16.000 EA	2,100.00000	33,600.00	860.00000	13,760.00	2,000.00000	32,000.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0080 0455133 2 14,937.000 SF SHEET PILING STEEL, TEMPORARY-CRITICAL	42.38000	633,030.06	22.00000	328,614.00	60.00000	896,220.00
0082 0455133326 (12000.000) SF (LS) STEEL SHEETPILING, TEMPORARY, NON-CRITICAL CANTILEVER 44118815201	35,000.00000	35,000.00	505,000.00000	505,000.00	600,000.00000	600,000.00
0085 0455133 3 9,642.000 SF SHEET PILING STEEL, F&I PERMANENT	99.85000	962,753.70	60.00000	578,520.00	75.00000	723,150.00
0090 0455137 12.000 EA LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	730.00000	8,760.00	1,150.00000	13,800.00	5,000.00000	60,000.00
0095 0455143 3 217.000 LF TEST PILES-PRESTRESSED CONCRETE,18" SQ	180.00000	39,060.00	575.00000	124,775.00	200.00000	43,400.00
0100 0458 1 11 56.000 LF BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	80.00000	4,480.00	45.00000	2,520.00	60.00000	3,360.00
0105 0521 5 13 246.000 LF CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	315.00000	77,490.00	150.00000	36,900.00	250.00000	61,500.00
0110 0530 3 3 427.300 TN RIPRAP- RUBBLE, BANK AND SHORE	98.00000	41,875.40	125.80000	53,754.34	135.00000	57,685.50

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0115 0530 74 BEDDING STONE 159.100 TN	101.00000	16,069.10	151.99000	24,181.61	125.00000	19,887.50
0120 0630 2 16 CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS 738.000 LF	26.00000	19,188.00	15.00000	11,070.00	5.00000	3,690.00
0125 0635 3 13 JUNCTION BOX, FURNISH & INSTALL, EMBEDDED 4.000 EA	1,550.00000	6,200.00	1,800.00000	7,200.00	125.00000	500.00
0001 Structures Section Totals:		**$3,229,960.26**		**$3,152,823.20**		**$4,133,053.00**
SECTION: 0002 Roadway						
0130 0101 1 MOBILIZATION 44118815201 (1.000) LS	500,000.00000	500,000.00	542,553.00000	542,553.00	500,000.00000	500,000.00
0135 0102 1 MAINTENANCE OF TRAFFIC 44118815201 (310.000) DA (LS)	100,000.00000	100,000.00	42,000.00000	42,000.00	25,000.00000	25,000.00
0140 0102 60 WORK ZONE SIGN 10,368.000 ED	0.30000	3,110.40	0.30000	3,110.40	0.35000	3,628.80
0145 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD 6,480.000 ED	0.15000	972.00	0.12000	777.60	0.15000	972.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0150 0102 99 1,620.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	20.00000	32,400.00	15.50000	25,110.00	18.00000	29,160.00
0155 0102115 1,240.000 ED TYPE III BARRICADE	0.61000	756.40	0.35000	434.00	0.40000	496.00
0160 0104 10 3 1,019.000 LF SEDIMENT BARRIER	4.80000	4,891.20	10.00000	10,190.00	5.50000	5,604.50
0165 0104 11 634.000 LF FLOATING TURBIDITY BARRIER	38.00000	24,092.00	30.00000	19,020.00	19.00000	12,046.00
0170 0104 12 295.000 LF STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	78.00000	23,010.00	20.00000	5,900.00	25.00000	7,375.00
0175 0110 1 1 (1.340) AC (LS) CLEARING & GRUBBING 44118815201	50,000.00000	50,000.00	535,225.00000	535,225.00	60,000.00000	60,000.00
0180 0120 1 1,124.800 CY REGULAR EXCAVATION	18.00000	20,246.40	5.75000	6,467.60	20.00000	22,496.00
0185 0120 4 1,489.600 CY SUBSOIL EXCAVATION	75.00000	111,720.00	11.75000	17,502.80	20.00000	29,792.00
0190 0120 6 1,707.700 CY EMBANKMENT	39.00000	66,600.30	19.50000	33,300.15	42.00000	71,723.40

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0195 0160 4 1,541.000 SY TYPE B STABILIZATION	12.00000	18,492.00	10.50000	16,180.50	23.00000	35,443.00
0200 0285701 133.000 SY OPTIONAL BASE, BASE GROUP 01	47.00000	6,251.00	12.50000	1,662.50	27.00000	3,591.00
0205 0285706 1,203.000 SY OPTIONAL BASE, BASE GROUP 06	33.00000	39,699.00	25.00000	30,075.00	31.00000	37,293.00
0210 0334 1 52 89.500 TN SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	192.00000	17,184.00	230.00000	20,585.00	245.00000	21,927.50
0215 0337 7 81 108.200 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	215.00000	23,263.00	260.00000	28,132.00	245.00000	26,509.00
0220 0339 1 34.600 TN MISCELLANEOUS ASPHALT PAVEMENT	384.00000	13,286.40	255.00000	8,823.00	410.00000	14,186.00
0225 0400 1 30 25.200 CY CONCRETE, CLASS I (SEAL)	305.00000	7,686.00	810.00000	20,412.00	2,500.00000	63,000.00
0230 0400 4 1 119.000 CY CONCRETE CLASS IV, CULVERTS	2,150.00000	255,850.00	2,800.00000	333,200.00	2,400.00000	285,600.00
0235 0415 1 1 19,200.000 LB REINFORCING STEEL- ROADWAY	3.70000	71,040.00	1.50000	28,800.00	3.25000	62,400.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0240 0425 1701 INLETS, GUTTER, TYPE S, <10' 4.000 EA	6,500.00000	26,000.00	6,305.00000	25,220.00	4,700.00000	18,800.00
0245 0425 1881 INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <=10' 4.000 EA	8,122.00000	32,488.00	7,140.00000	28,560.00	6,300.00000	25,200.00
0250 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD 145.000 LF	150.00000	21,750.00	158.00000	22,910.00	130.00000	18,850.00
0255 0430611225 U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 18"PIPE 2.000 EA	6,500.00000	13,000.00	6,065.00000	12,130.00	5,700.00000	11,400.00
0260 0430611325 U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE 2.000 EA	6,500.00000	13,000.00	6,170.00000	12,340.00	6,300.00000	12,600.00
0265 0520 6 SHOULDER GUTTER- CONCRETE 381.000 LF	610.00000	232,410.00	49.00000	18,669.00	58.00000	22,098.00
0270 0521 8 7 CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE 46.000 LF	385.00000	17,710.00	365.00000	16,790.00	600.00000	27,600.00
0275 0521 72 40 SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT 269.000 LF	385.00000	103,565.00	475.00000	127,775.00	600.00000	161,400.00
0280 0521 72 42 SHOULDER CONCRETE BARRIER, 38" TRENCH FOOTING SECTION 20.000 LF	385.00000	7,700.00	660.00000	13,200.00	1,800.00000	36,000.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0285 0530 3 3 80.500 TN RIPRAP- RUBBLE, BANK AND SHORE	315.00000	25,357.50	255.00000	20,527.50	140.00000	11,270.00
0290 0530 3 4 6.400 TN RIPRAP, RUBBLE, F&I, DITCH LINING	150.00000	960.00	230.00000	1,472.00	315.00000	2,016.00
0295 0530 74 34.600 TN BEDDING STONE	101.00000	3,494.60	100.00000	3,460.00	175.00000	6,055.00
0300 0536 1 0 696.000 LF GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	38.50000	26,796.00	22.00000	15,312.00	24.00000	16,704.00
0305 0536 7 3 10.000 EA SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	715.00000	7,150.00	200.00000	2,000.00	220.00000	2,200.00
0310 0536 8111 2.000 EA GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	4,565.00000	9,130.00	3,000.00000	6,000.00	3,100.00000	6,200.00
0315 0536 8113 2.000 EA GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	4,565.00000	9,130.00	2,500.00000	5,000.00	2,600.00000	5,200.00
0320 0536 73 1,104.000 LF GUARDRAIL REMOVAL	6.00000	6,624.00	2.00000	2,208.00	2.25000	2,484.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0325 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 2.000 EA	3,200.00000	6,400.00	2,000.00000	4,000.00	2,100.00000	4,200.00
0330 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 2.000 EA	5,300.00000	10,600.00	3,000.00000	6,000.00	3,200.00000	6,400.00
0335 0570 1 2 PERFORMANCE TURF, SOD 1,267.000 SY	4.80000	6,081.60	15.00000	19,005.00	8.00000	10,136.00
0340 0630 2 16 CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS 1,004.000 LF	26.00000	26,104.00	15.00000	15,060.00	5.00000	5,020.00
0002 Roadway Section Totals:		**$1,996,000.80**		**$2,107,099.05**		**$1,730,076.20**
SECTION: 0003 Signing						
0345 0700 1111 SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF 3.000 EA	770.00000	2,310.00	500.00000	1,500.00	515.00000	1,545.00
0350 0700 1500 SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE 1.000 EA	110.00000	110.00	120.00000	120.00	125.00000	125.00
0355 0700 1600 SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE 4.000 EA	66.00000	264.00	50.00000	200.00	52.00000	208.00

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) RBM CONTRACTING SERVICES, LLC		(2) SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC		(3) F & W CONSTRUCTION COMPANY, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0360 0706 1 3 RAISED PAVEMENT MARKER, TYPE B 28.000 EA	15.00000	420.00	6.00000	168.00	6.50000	182.00
0365 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 0.163 GM	8,250.00000	1,344.75	7,000.00000	1,141.00	7,100.00000	1,157.30
0370 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" 0.163 GM	8,250.00000	1,344.75	7,000.00000	1,141.00	7,100.00000	1,157.30
0375 0713103101 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES 0.039 GM	50,000.00000	1,950.00	35,000.00000	1,365.00	35,500.00000	1,384.50
0380 0713103201 PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES 0.039 GM	50,000.00000	1,950.00	35,000.00000	1,365.00	35,500.00000	1,384.50
0003 Signing Section Totals:		**$9,693.50**		**$7,000.00**		**$7,143.60**
Contract Grand Totals:		**$5,235,654.56**		**$5,266,922.25**		**5,870,272.80**

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (1488.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 44118815201	255,000.00000	255,000.00	201,500.00000	201,500.00		
0010 0400 1 30 65.400 CY CONCRETE, CLASS I (SEAL)	1,550.00000	101,370.00	650.00000	42,510.00		
0015 0400 2 4 92.800 CY CONC CLASS II, BRIDGE SUPERSTRUCTURE	2,540.00000	235,712.00	1,900.00000	176,320.00		
0020 0400 2 10 43.700 CY CONCRETE CLASS II, APPROACH SLABS	1,000.00000	43,700.00	1,300.00000	56,810.00		
0025 0400 4 5 72.800 CY CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	4,640.00000	337,792.00	4,500.00000	327,600.00		
0030 0400 4 8 158.800 CY CONC CLASS IV, BULKHEAD	1,758.77000	279,292.68	1,300.00000	206,440.00		
0035 0400 7 1 192.000 SY BRIDGE DECK GROOVING	25.00000	4,800.00	65.00000	12,480.00		
0040 0400148 2.600 CF PLAIN NEOPRENE BEARING PADS	1,600.00000	4,160.00	4,500.00000	11,700.00		
0045 0415 1 4 27,719.000 LB REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	2.00000	55,438.00	2.00000	55,438.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0050 0415 1 5 REINFORCING STEEL- BRIDGE SUBSTRUCTURE 23,906.000 LB	2.00000	47,812.00	4.50000	107,577.00		
0055 0415 1 8 REINFORCING STEEL- BULKHEAD 7,233.000 LB	2.00000	14,466.00	4.00000	28,932.00		
0060 0415 1 9 REINFORCING STEEL- APPROACH SLABS 8,580.000 LB	2.00000	17,160.00	3.00000	25,740.00		
0065 0455 20 1 PILE INSPECTION, DRIVEN PILE 16.000 EA	750.00000	12,000.00	1,250.00000	20,000.00		
0070 0455 34 3 PRESTRESSED CONCRETE PILING, 18" SQ 684.000 LF	220.00000	150,480.00	235.00000	160,740.00		
0075 0455115 PILE REDRIVE 16.000 EA	250.00000	4,000.00	1,200.00000	19,200.00		
0080 0455133 2 SHEET PILING STEEL, TEMPORARY- CRITICAL 14,937.000 SF	65.00000	970,905.00	77.00000	1,150,149.00		
0082 0455133326 STEEL SHEETPILING, TEMPORARY, NON-CRITICAL CANTILEVER 44118815201 (12000.000) SF (LS)	723,000.00000	723,000.00	199,500.00000	199,500.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0085 0455133 3 SHEET PILING STEEL, F&I PERMANENT 9,642.000 SF	70.00000	674,940.00	89.00000	858,138.00		
0090 0455137 LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS 12.000 EA	4,500.00000	54,000.00	2,500.00000	30,000.00		
0095 0455143 3 TEST PILES-PRESTRESSED CONCRETE,18" SQ 217.000 LF	270.00000	58,590.00	335.00000	72,695.00		
0100 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD 56.000 LF	85.00000	4,760.00	100.00000	5,600.00		
0105 0521 5 13 CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE 246.000 LF	275.00000	67,650.00	175.00000	43,050.00		
0110 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE 427.300 TN	130.00000	55,549.00	170.00000	72,641.00		
0115 0530 74 BEDDING STONE 159.100 TN	140.00000	22,274.00	190.00000	30,229.00		
0120 0630 2 16 CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS 738.000 LF	18.00000	13,284.00	30.00000	22,140.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0125 0635 3 13 4.000 EA JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	315.00000	1,260.00	1,000.00000	4,000.00		
0001 Structures Section Totals:		**$4,209,394.68**		**$3,941,129.00**		
SECTION: 0002 Roadway						
0130 0101 1 (1.000) LS MOBILIZATION 44118815201	544,842.75000	544,842.75	589,000.00000	589,000.00		
0135 0102 1 (310.000) DA (LS) MAINTENANCE OF TRAFFIC 44118815201	104,000.00000	104,000.00	30,000.00000	30,000.00		
0140 0102 60 10,368.000 ED WORK ZONE SIGN	0.30000	3,110.40	0.35000	3,628.80		
0145 0102 74 1 6,480.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.12000	777.60	0.20000	1,296.00		
0150 0102 99 1,620.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	15.50000	25,110.00	18.00000	29,160.00		
0155 0102115 1,240.000 ED TYPE III BARRICADE	0.35000	434.00	0.45000	558.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0160 0104 10 3 SEDIMENT BARRIER 1,019.000 LF	4.00000	4,076.00	7.00000	7,133.00		
0165 0104 11 FLOATING TURBIDITY BARRIER 634.000 LF	17.86000	11,323.24	30.00000	19,020.00		
0170 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC 295.000 LF	8.77000	2,587.15	25.00000	7,375.00		
0175 0110 1 1 CLEARING & GRUBBING 44118815201 (1.340) AC (LS)	22,000.00000	22,000.00	85,000.00000	85,000.00		
0180 0120 1 REGULAR EXCAVATION 1,124.800 CY	17.22000	19,369.06	42.00000	47,241.60		
0185 0120 4 SUBSOIL EXCAVATION 1,489.600 CY	22.22000	33,098.91	38.00000	56,604.80		
0190 0120 6 EMBANKMENT 1,707.700 CY	34.15000	58,317.96	60.00000	102,462.00		
0195 0160 4 TYPE B STABILIZATION 1,541.000 SY	12.00000	18,492.00	33.00000	50,853.00		
0200 0285701 OPTIONAL BASE, BASE GROUP 01 133.000 SY	30.00000	3,990.00	38.00000	5,054.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units ( ) indicates item is bid as Lump Sum	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0205 0285706 OPTIONAL BASE, BASE GROUP 06 1,203.000 SY	25.00000	30,075.00	41.00000	49,323.00		
0210 0334 1 52 SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22 89.500 TN	290.00000	25,955.00	285.00000	25,507.50		
0215 0337 7 81 ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22 108.200 TN	290.00000	31,378.00	300.00000	32,460.00		
0220 0339 1 MISCELLANEOUS ASPHALT PAVEMENT 34.600 TN	420.00000	14,532.00	325.00000	11,245.00		
0225 0400 1 30 CONCRETE, CLASS I (SEAL) 25.200 CY	1,550.00000	39,060.00	650.00000	16,380.00		
0230 0400 4 1 CONCRETE CLASS IV, CULVERTS 119.000 CY	2,286.64000	272,110.16	3,085.00000	367,115.00		
0235 0415 1 1 REINFORCING STEEL- ROADWAY 19,200.000 LB	1.20000	23,040.00	2.45000	47,040.00		
0240 0425 1701 INLETS, GUTTER, TYPE S, <10' 4.000 EA	8,221.88000	32,887.52	7,250.00000	29,000.00		
0245 0425 1881 INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <=10' 4.000 EA	7,236.88000	28,947.52	9,400.00000	37,600.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0250 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD 145.000 LF	167.40000	24,273.00	240.00000	34,800.00		
0255 0430611225 U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 18"PIPE 2.000 EA	7,373.88000	14,747.76	7,500.00000	15,000.00		
0260 0430611325 U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE 2.000 EA	7,009.50000	14,019.00	7,500.00000	15,000.00		
0265 0520 6 SHOULDER GUTTER- CONCRETE 381.000 LF	45.00000	17,145.00	92.00000	35,052.00		
0270 0521 8 7 CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE 46.000 LF	566.80000	26,072.80	1,025.00000	47,150.00		
0275 0521 72 40 SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT 269.000 LF	548.80000	147,627.20	600.00000	161,400.00		
0280 0521 72 42 SHOULDER CONCRETE BARRIER, 38" TRENCH FOOTING SECTION 20.000 LF	685.80000	13,716.00	1,100.00000	22,000.00		
0285 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE 80.500 TN	160.00000	12,880.00	160.00000	12,880.00		
0290 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING 6.400 TN	160.00000	1,024.00	500.00000	3,200.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0295 0530 74 BEDDING STONE 34.600 TN	160.00000	5,536.00	300.00000	10,380.00		
0300 0536 1 0 GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2 696.000 LF	22.00000	15,312.00	25.00000	17,400.00		
0305 0536 7 3 SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT 10.000 EA	200.00000	2,000.00	225.00000	2,250.00		
0310 0536 8111 GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2 2.000 EA	3,000.00000	6,000.00	3,350.00000	6,700.00		
0315 0536 8113 GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING 2.000 EA	2,500.00000	5,000.00	2,800.00000	5,600.00		
0320 0536 73 GUARDRAIL REMOVAL 1,104.000 LF	2.00000	2,208.00	6.00000	6,624.00		
0325 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 2.000 EA	2,000.00000	4,000.00	2,250.00000	4,500.00		
0330 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 2.000 EA	3,000.00000	6,000.00	3,400.00000	6,800.00		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0335 0570 1 2 PERFORMANCE TURF, SOD 1,267.000 SY	5.00000	6,335.00	7.00000	8,869.00		
0340 0630 2 16 CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS 1,004.000 LF	18.00000	18,072.00	25.65000	25,752.60		
0002 Roadway Section Totals:		**$1,691,482.03**		**$2,091,414.30**		
SECTION: 0003 Signing						
0345 0700 1111 SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF 3.000 EA	500.00000	1,500.00	600.00000	1,800.00		
0350 0700 1500 SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE 1.000 EA	120.00000	120.00	150.00000	150.00		
0355 0700 1600 SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE 4.000 EA	50.00000	200.00	100.00000	400.00		
0360 0706 1 3 RAISED PAVEMENT MARKER, TYPE B 28.000 EA	6.00000	168.00	7.00000	196.00		
0365 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 0.163 GM	7,000.00000	1,141.00	7,850.00000	1,279.55		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MURPHREE BRIDGE CORPORATION		(5) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0370 0711 16201 0.163 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" GM	7,000.00000	1,141.00	7,850.00000	1,279.55		
0375 0713103101 0.039 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES GM	35,000.00000	1,365.00	40,000.00000	1,560.00		
0380 0713103201 0.039 PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES GM	35,000.00000	1,365.00	40,000.00000	1,560.00		
0003 Signing Section Totals:		**$7,000.00**		**$8,225.10**		
Contract Grand Totals:		**$5,907,876.71**		**$6,040,768.40**		

Letting: CT261028 October 28, 2026 **Call Order:** 012 **Contract:** T3970

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

A Mirza Rezazadeh 11/10/2026

Manager, Contracts Administration Office