

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250528	Call Order: 014	Proposal: T3938	District:03
Counties:	HOLMES			
Road Name:	SR 10 (US 90) AND SR 79			
Limits:	FROM E OF BANFILL AVE TO E OF HUBBARD ST AND FROM SR 10 (US 90) TO N OF CR 177			
Project(s):	21916535201	Federal Aid No:	N/A	
Project(s):	21916535202	Federal Aid No:	D324003B	
Project(s):	21916535203	Federal Aid No:	N/A	
Project(s):	43626925201(*)	Federal Aid No:	N/A	
Project(s):	43626925202	Federal Aid No:	N/A	
Project(s):	43626925203	Federal Aid No:	D324041B	
Total Roadway Length:	1.996 Miles	Contract Days:	413	
Total Bridge Length:	0.000 Miles	Letting Date:	05/28/25	
Total Proposal Length:	1.996 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$5,545,966.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of resurfacing on SR 10 US 90 and SR 79 under FPIDs 436269-2-52-01 GW 219165-3-52-01. FPID 436269-2-52-01 is the lead and consists of resurfacing on SR 10 US 90 from East of Banfill Ave to East of Hubbard Street. Additional work includes FPID 436269-2-52-02 UWHC manhole adjustments and FPID 436269-2-52-03 drainage improvements. FPID 219165-3-52-01 consists of resurfacing on SR 79 from SR 10 US 90 to North of CR 177. Additional work to be done includes FPID 219165-3-52-02 sidewalk rehabilitation and FPID 219165-3-52-03 UWHC manhole and valve box adjustments. All work is to be done in Holmes County.

Call Order: 014 Proposal: T3938

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21916535201)	LS	1.000
	0101- 1-	MOBILIZATION (21916535202)	LS	1.000
	0101- 1-	MOBILIZATION (43626925201)	LS	1.000
	0101- 1-	MOBILIZATION (43626925203)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21916535201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21916535202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43626925201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43626925203)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	2.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	464.000
	0102- 60-	WORK ZONE SIGN	ED	55,216.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	72,945.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	11,052.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,616.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,652.000

Call Order: 014 Proposal: T3938

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,652.000
	0102-115-	TYPE III BARRICADE	ED	3,074.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	413.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,381.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	24.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	125.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	5.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	42.000
	0107- 1-	LITTER REMOVAL	AC	252.100
	0107- 2-	MOWING	AC	201.560
	0110- 1- 1	CLEARING & GRUBBING (21916535201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43626925201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	944.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	3.000
	0120- 1-	REGULAR EXCAVATION	CY	199.500
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	63.600
	0120- 6-	EMBANKMENT	CY	14.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (21916535201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	133.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	133.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	132.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	108,065.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	25,851.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	10.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	14,055.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	27.300
	0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	12.500
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	1,250.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	6.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	18.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0425- 10-	YARD DRAIN	EA	1.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0425- 82-	REPLACE GRATE	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	60.000

Call Order: 014 Proposal: T3938

ALT	Item	Description	Unit	Quantity
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	39.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	10.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD (43626925203)	LF	291.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	109.000
	0430-175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	LF	295.000
	0430-175-254	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 54"S/CD	LF	15.000
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	110.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	34.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	113.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	962.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	155.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	174.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	706.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	682.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	12.000
	0527- 2-	DETECTABLE WARNINGS	SF	653.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	188.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,625.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	4,502.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,642.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.296
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,236.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,108.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,122.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.552
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.092
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	182.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.658
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.034
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.046
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21916535201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21916535202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43626925201)	LS	1.000

Call Order: 014 Proposal: T3938

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43626925203)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	4.529
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	12.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	9.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	14.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,398.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21916535201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43626925201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,327.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	147.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,043.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.046
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	136.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	887.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.523
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	50.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,276.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	274.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.512
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.300
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.326
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.638
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	428.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	11.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	7.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	6.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000

Call Order: 014 Proposal: T3938

ALT	Item	Description	Unit	Quantity
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	14.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	13.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	8.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	14.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	2.000