

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260225	Call Order: 009	Proposal: T2A60	District:02
Counties:	MADISON			
Road Name:	SR 55 (US 221)			
Limits:	FROM SR 10 (US 90) TO THE JEFFERSON CO LINE			
Project(s):	21050545201(*)	Federal Aid No:	D225100B	
Total Roadway Length:	6.730 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	02/25/26	
Total Proposal Length:	6.730 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$6,335,645.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing, guardrail, and other incidental construction on SR 55 (US 221) from SR 10 (US 90) to the Jefferson County Line in Madison County.

Call Order: 009 Proposal: T2A60

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21050545201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21050545201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	16.000
	0102- 60-	WORK ZONE SIGN	ED	9,000.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	663.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	2,750.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,200.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	12.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	776.000
	0102-115-	TYPE III BARRICADE	ED	900.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,958.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	429.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	361.440
	0107- 2-	MOWING	AC	312.480
	0110- 1- 1	CLEARING & GRUBBING (21050545201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	288.000
	0120- 1-	REGULAR EXCAVATION	CY	41.000
	0120- 6-	EMBANKMENT	CY	619.000
	0160- 4-	TYPE B STABILIZATION	SY	2,943.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	4,003.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	94,591.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	44,678.000

Call Order: 009 Proposal: T2A60

ALT	Item	Description	Unit	Quantity
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	7,805.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	11,489.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	191.600
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	220.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	420.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,213.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	121.000
	0536- 73-	GUARDRAIL REMOVAL	LF	980.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	12.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	30,284.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,318.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	27.260
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	48.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	136.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.228
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	18.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.672
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	248.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	9.346
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21050545201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	18.482
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	73.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	8.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	56.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	36.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	32.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,568.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21050545201)	LS	1.000

Call Order: 009 Proposal: T2A60

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	156.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	235.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.110
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	9.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	338.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.045
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	13.493
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.765
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.163