

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT250730	Call Order: 003	Proposal: T1927	District:01
Counties:	HARDEE			
Road Name:	WEST MAIN ST			
Limits:	FROM HANCHEY RD TO W OF FLORIDA AVE			
Project(s):	44477325201(*)	Federal Aid No: D125057B		
Total Roadway Length:	0.389 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	07/30/25	
Total Proposal Length:	0.389 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$485,927.00			

Please read the full advertisement

Description:

The improvements under this Contract consist of sidewalk, turnouts, curb and gutter, drainage and signing and pavement markings along West Main Street from Hanchey Road to West of Florida Avenue in Hardee County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtml>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/construction/training/ctqp/smallbusiness/smallbusinessstraining.shtml>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: T1927

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44477315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44477315201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	188.900
	0102- 60-	WORK ZONE SIGN	ED	2,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,500.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	228.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,020.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0110- 1- 1	CLEARING & GRUBBING (44477315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	87.000
	0120- 1-	REGULAR EXCAVATION	CY	149.200
	0120- 6-	EMBANKMENT	CY	327.800
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	395.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	32.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	32.600
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	33.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	29.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	497.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,048.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	280.000
	0527- 2-	DETECTABLE WARNINGS	SF	161.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,216.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	482.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44477315201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	245.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	16.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	195.000