

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250827	Call Order: 008	Proposal: T4715	District:04
Counties:	BROWARD			
Road Name:	SR 817 (UNIVERSITY DR)			
Limits:	FROM NOVA DR TO SR 84			
Project(s):	44562415201(*)	Federal Aid No:	D425024B	
Project(s):	44562415202	Federal Aid No:	N/A	
Project(s):	44562415203	Federal Aid No:	N/A	
Total Roadway Length:	0.770 Miles	Contract Days:	406	
Total Bridge Length:	0.000 Miles	Letting Date:	08/27/25	
Total Proposal Length:	0.770 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$8,490,256.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, MOT (standard, special detours, traffic control officer, barrier, barricade, crash cushion, signalization, traffic detention, arrow board, PCMS), protections (sediment, inlet), earthwork (excavation, embankment), milling and resurfacing, concrete (gravity wall, curb, curb and gutter, shoulder gutter, shoulder barrier, ditch, sidewalk, driveways), signing (single-column, multi-column, panel, overhead static, reflective strip), pavement markings (painted, RPM, object marker, detectable, thermoplastic, permanent tape, removable tape, bike lane), pedestrian railing, fencing, guardrail, signalization (concrete pole, aluminum pole, mast arm, vehicular signal, vehicular detection, pedestrian signal, pedestrian detection, controllers), lighting (conduit, distribution system, light pole, luminaire), drainage (inlets, pipe culvert, flared end, mitered end, trench drain), utilities (manholes, valve boxes, adjustments), electrical (power service, load center, service wire), and sod along State Road 817 (University Drive) for 0.77 miles from south of Nova Drive to State Road 84 in the Town of Davie, Broward County.

Call Order: 008 Proposal: T4715

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44562415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44562415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44562415201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44562415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	252.000
	0102- 60-	WORK ZONE SIGN	ED	12,783.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	3,892.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,374.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	35,168.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	213,188.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	188.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	359.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	495.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,218.000

Call Order: 008 Proposal: T4715

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,218.000
	0102-115-	TYPE III BARRICADE	ED	3.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,206.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	126.650
	0107- 2-	MOWING	AC	100.060
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44562415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44562415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44562415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,751.000
	0120- 1-	REGULAR EXCAVATION	CY	3,165.700
	0120- 6-	EMBANKMENT	CY	2,397.000
	0160- 4-	TYPE B STABILIZATION	SY	5,604.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,593.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,007.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	1,686.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	317.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	25,733.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	93.700
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	304.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	2,457.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3.100
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	74.700
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	4.000
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	8.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 1-881	INLETS, BARRIER WALL, RIGID, CURB & GUTTER, <=10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	5.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	4.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	52.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	232.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	12.000

Call Order: 008 Proposal: T4715

ALT	Item	Description	Unit	Quantity
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	16.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	651.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	339.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	81.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	1,657.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	383.000
	0515- 2-211	PEDESTRIAN / BICYCLE RAILING, STEEL, 42" TYPE 1	LF	8.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,916.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	85.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	143.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	6.000
	0521- 1- 12	MEDIAN CONCRETE BARRIER, SHORT GRADE-SEPARATED	LF	32.000
	0521- 1- 13	MEDIAN CONCRETE BARRIER, TALL GRADE-SEPARATED	LF	153.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	472.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,634.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	5.000
	0527- 2-	DETECTABLE WARNINGS	SF	225.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	46.000
	0536- 73-	GUARDRAIL REMOVAL	LF	39.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	1.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	1,014.000
	0570- 1- 1	PERFORMANCE TURF	SY	4,047.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,635.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	206.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	196.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	15.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	15.000
	0695- 7-141	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 4, BASE MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	586.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.593
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.364
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,890.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	286.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,675.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.857

Call Order: 008 Proposal: T4715

ALT	Item	Description	Unit	Quantity
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.047
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.419
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	45.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.973
	0751- 35- 13	ARCHITECTURAL, BUS SHELTER, F&I, 101-150 SF	EA	1.000
	0751- 35- 15	ARCHITECTURAL, BUS SHELTER, F&I, GREATER THAN 200 SF	EA	1.000
	0751- 36- 11	BICYCLE RACK, FURNISH & INSTALL, 1-2 BICYCLES	EA	2.000
	0751- 37-	TRASH RECEPTACLE	EA	2.000
	0751- 38- 14	BENCH, F&I, STEEL	EA	2.000
	0751- 38- 50	BENCH, RELOCATE	EA	1.000
	0999- 16-	PARTNERING, DO NOT BID (44562415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44562415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44562415202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	14.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	10.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	2.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	1.000
	0700- 4-127	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	1.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0700- 4-622	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, SPAN	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	4.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	572.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	18.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44562415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,945.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	286.000

Call Order: 008 Proposal: T4715

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	313.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.209
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	33.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	34.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,380.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	11.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	17.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.668
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.201
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.702
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.068
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.728
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.236
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	355.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,844.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,331.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	31.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	198.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	15,315.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	6,833.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	6.000
	0715- 61-100	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 0' ARM LENGTH	EA	9.000
	0715- 61-552	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 15' ARM LENGTH	EA	10.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	9.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	25.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	283.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,576.000

Call Order: 008 Proposal: T4715

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	58.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,074.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	6.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	1.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	29.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	5.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	1.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
Section 0005 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	7.000
	0425- 6-	VALVE BOXES, ADJUST	EA	13.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44562415203)	LS	1.000
	1050- 18-005	UTILITY PIPE, PLUG & PLACE OUT OF SERVICE, 20-49.9"	LF	2,151.000