

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 010	Proposal: T2A88	District:02
Counties:	UNION			
Road Name:	SW 4TH AVE, SW 11TH ST AND S LAKE AVE			
Limits:	FROM SR 121 TO SR 121			
Project(s):	44124225201(*)	Federal Aid No:	D226065B	
Total Roadway Length:	1.075 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	10/28/26	
Total Proposal Length:	1.075 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	
Proposal Budget Estimate:	\$617,643.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of drainage improvements, curb & gutters, highway signing, sidewalks, sod, pavement markings and other incidental construction on Lake Butler Off-System Sidewalk SW 4th Ave.; SW 11th St.; S. Lake Ave. from SR 121 to SR 121 in Union County.

Call Order: 010 Proposal: T2A88

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44124225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44124225201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	34,350.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	15,300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,558.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0110- 1- 1	CLEARING & GRUBBING (44124225201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,095.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0110- 23-	TREE REMOVAL	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	650.100
	0120- 6-	EMBANKMENT	CY	224.200
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	8.900
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 10-	YARD DRAIN	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	198.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	14.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	14.000

Call Order: 010 Proposal: T2A88

ALT	Item	Description	Unit	Quantity
	0430-515-100	STRAIGHT CONCRETE ENDWALLS, 15", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-518-102	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	1.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	314.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	266.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	233.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	3,904.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	53.000
	0527- 2-	DETECTABLE WARNINGS	SF	871.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,750.000
	0751- 11-601	ARCHITECTURAL- SPECIAL, REMOVE (73'x8' covering with 12 poles)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44124225201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44124225201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,542.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	38.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	304.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	806.000