

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250827	Call Order: 002	Proposal: T2A00	District:02
Counties:	SUWANNEE			
Road Name:	SR 51 (US 129)			
Limits:	FROM N OF I-10 (SR 8) TO HAMILTON CO LINE			
Project(s):	21078145201(*)	Federal Aid No:	D224087B	
Total Roadway Length:	4.482 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	08/27/25	
Total Proposal Length:	4.482 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	
Proposal Budget Estimate:	\$5,079,052.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, drainage improvements, highway signing, and other incidental construction on SR 51 (US 129) in Suwannee County from North of SR 8 (I-10) to the Hamilton County Line.

Call Order: 002 Proposal: T2A00

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21078145201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21078145201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	200.000
	0102- 60-	WORK ZONE SIGN	ED	7,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	28,050.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	164.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	504.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	143.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	297.920
	0107- 2-	MOWING	AC	270.830
	0110- 1- 1	CLEARING & GRUBBING (21078145201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	159.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,616.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	135.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	71,997.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	26,558.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	7,922.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	8,142.200
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	152.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	11.400
	0530- 74-	BEDDING STONE	TN	8.300
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	18,350.000

Call Order: 002 Proposal: T2A00

ALT	Item	Description	Unit	Quantity
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,110.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.163
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	355.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	7.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.715
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.338
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21078145201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	11.598
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	33.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	26.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	6.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	18.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	9.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,110.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21078145201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	174.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	353.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	9.380
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.136
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.115
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.338
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.898
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.930