

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250528	Call Order: 016	Proposal: T3967	District:03
Counties:	ESCAMBIA			
Road Name:	SR 292 (SORRENTO RD)			
Limits:	FROM CR 293 (BAUER RD) TO CR 292A (GULF BEACH HWY)			
Project(s):	45081415201(*)	Federal Aid No:	D324074B	
Project(s):	45081415202	Federal Aid No:	N/A	
Project(s):	45081425201	Federal Aid No:	D323102B	
Total Roadway Length:	3.661 Miles	Contract Days:	450	
Total Bridge Length:	0.004 Miles	Letting Date:	05/28/25	
Total Proposal Length:	3.665 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$6,555,983.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of FPID 450814-1-52-01: milling and resurfacing, turn lane widening, intersection improvements, signing and pavement markings and signalization along SR 292 Sorrento Rd from CR 293 (Bauer Rd) to CR 292A (Gulf Beach Hwy); FPID 450814-1-52-02: utility work by highway contractor along SR 292 Sorrento Rd/Gulf Beach Hwy from CR 293 to CR 292A; and FPID 450814-2-52-01: add paved shoulders along SR 292 Sorrento Rd from CR 293 (Bauer Rd) to CR 292A (Gulf Beach Hwy), all work to be done in Escambia County.

Call Order: 016 Proposal: T3967

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45081415201)	LS	1.000
	0101- 1-	MOBILIZATION (45081425201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45081415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45081425201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	56.000
	0102- 60-	WORK ZONE SIGN	ED	15,750.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	23,400.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	928.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	450.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	450.000
	0104- 6-	TEMPORARY SLOPE DRAIN / RUNOFF CONTROL STRUCTURE	LF	135.000
	0104- 10- 3	SEDIMENT BARRIER	LF	28,521.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	449.820
	0107- 2-	MOWING	AC	449.820
	0110- 1- 1	CLEARING & GRUBBING (45081415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45081425201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	441.000
	0120- 1-	REGULAR EXCAVATION	CY	2,391.400
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,931.500

Call Order: 016 Proposal: T3967

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	1,279.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	590.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	15,948.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	856.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	17,911.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	1,592.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	38,500.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	16,458.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	33.100
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2,311.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	9,062.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	45.100
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	3.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	128.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	16.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 36"SD	LF	77.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	349.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	48.000
	0430-175-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	8.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	LF	332.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	7.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	1.000
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	3.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	4.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	263.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	126.000
	0527- 2-	DETECTABLE WARNINGS	SF	89.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	12.000
	0530- 74-	BEDDING STONE	TN	8.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	697.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	3.000
	0536- 73-	GUARDRAIL REMOVAL	LF	549.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	35,426.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,368.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.412

Call Order: 016 Proposal: T3967

ALT	Item	Description	Unit	Quantity
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.149
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	813.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	378.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	960.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.004
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.470
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	70.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.022
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	757.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.648
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.061
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45081415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45081425201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	7.418
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	20.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	19.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	9.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,368.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45081415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	813.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	378.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	281.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.470
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	60.000

Call Order: 016 Proposal: T3967

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	757.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.061
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	679.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	8.412
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.149
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.004
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.022
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.648
Section 0003 Signalization				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	169.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	450.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	18.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	26.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	12.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	6.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	9.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000

Call Order: 016 Proposal: T3967

ALT	Item	Description	Unit	Quantity
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000