

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 008	Proposal: T2A86	District:02
Counties:	PUTNAM			
Road Name:	SR 100			
Limits:	FROM CLAY COUNTY LINE TO STJOHNS RIVER WATER MANAGEMENT DISTRICT			
Project(s):	21001435201(*)	Federal Aid No:	D226028B	
Total Roadway Length:	18.726 Miles	Contract Days:	300	
Total Bridge Length:	0.082 Miles	Letting Date:	10/28/26	
Total Proposal Length:	18.808 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$11,454,574.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, shoulder treatment, drainage improvements, base work, highway signing, guardrail, and other incidental construction on SR 100 from Clay County Line to St. Johns Water Management District in Putnam County.

Call Order: 008 Proposal: T2A86

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	644.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	25.700
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (21001435201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21001435201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (21001435201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (21001435201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	10.000
	0102- 60-	WORK ZONE SIGN	ED	12,954.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,500.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	750.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	59,795.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	846.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	628.000
	0102-115-	TYPE III BARRICADE	ED	326.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	179.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,889.000
	0107- 1-	LITTER REMOVAL	AC	990.430
	0107- 2-	MOWING	AC	731.740
	0110- 1- 1	CLEARING & GRUBBING (21001435201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	214.400

Call Order: 008 Proposal: T2A86

ALT	Item	Description	Unit	Quantity
	0120- 4-	SUBSOIL EXCAVATION	CY	190.800
	0120- 6-	EMBANKMENT	CY	987.300
	0160- 4-	TYPE B STABILIZATION	SY	1,244.000
	0173- 76-	GROUT PIPE INSTALLATION	LF	280.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	65.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,774.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	834.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	7,416.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	376,168.000
	0327- 70- 18	MILLING EXISTING ASPHALT PAVEMENT, 5 1/2" AVG DEPTH	SY	841.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,337.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	42,404.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	28.800
	0425- 82-	REPLACE GRATE	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	8.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	34.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	10.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	6.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	1.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	84.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,184.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	257.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,184.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	66,800.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	9,362.700
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.859
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	31.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.022
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.594
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	252.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.055
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21001435201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	51.103
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	40.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	17.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	29.000

Call Order: 008 Proposal: T2A86

ALT	Item	Description	Unit	Quantity
	0700- 2-111	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	4.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	14.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	14.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000
	0700-142-112	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, 12-20 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	1.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	42.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	32.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	8.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,745.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21001435201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,215.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	318.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.115
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	33.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	640.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	37.873
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	19.560
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	11.635
Section 0004 Signalization				
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000