

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 002	Proposal: T1943	District:01
Counties:	CHARLOTTE			
Road Name:	SR 776			
Limits:	AT OCEANSPRAY BLVD			
Project(s):	45136015201(*)	Federal Aid No:	D126042B	
Total Roadway Length:	0.636 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	09/30/26	
Total Proposal Length:	0.636 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	

Proposal Budget Estimate: \$1,154,500.00

Please read the full advertisement

Description:

The improvements under this project consist of milling and resurfacing, drainage, curb and gutter, traffic separators and signing and pavement markings on SR 776 at Oceanspray Blvd. in Charlotte County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/construction/training/ctqp/smallbusiness/smallbusinessstraining.shtm>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

Call Order: 002 Proposal: T1943

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45136015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45136015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	240.000
	0102- 60-	WORK ZONE SIGN	ED	20,040.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,716.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	27,120.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000

Call Order: 002 Proposal: T1943

ALT	Item	Description	Unit	Quantity
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	233.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	30.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	30.000
	0102-115-	TYPE III BARRICADE	ED	420.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	480.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	480.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,974.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	34.270
	0107- 2-	MOWING	AC	32.340
	0110- 1- 1	CLEARING & GRUBBING (45136015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	98.000
	0120- 1-	REGULAR EXCAVATION	CY	1,233.000
	0120- 6-	EMBANKMENT	CY	638.400
	0160- 4-	TYPE B STABILIZATION	SY	3,343.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	2,557.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	2,020.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	663.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	228.800
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	521.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	128.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,428.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.141
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.324
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	713.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	13.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	24.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.427
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	115.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.036
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45136015201)	LS	1.000
Section 0002 Signing				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	120.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	13.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000

Call Order: 002 Proposal: T1943

ALT	Item	Description	Unit	Quantity
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	14.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	18.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	4.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	121.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45136015201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	713.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	13.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	24.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	115.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.036
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.141
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.324
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.427