

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 016	Proposal: T7622	District:07
Counties:	PINELLAS			
Road Name:	SR 699 (GULF BLVD)			
Limits:	FROM SR 682 (PINELLAS BAYWAY) TO SR 688 (WALSINGHAM RD)			
Project(s):	45631225201(*)	Federal Aid No:	E242020E	
Total Roadway Length:	14.604 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	09/30/26	
Total Proposal Length:	14.604 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	
Proposal Budget Estimate:	\$801,738.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of emergency repairs. Repairs include drainage inlet repair, signage and RPMs replacement, sidewalk, driveway and shoulder reconstruction, and milling and resurfacing.

Call Order: 016 Proposal: T7622

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45631225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45631225201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	288.000
	0102- 60-	WORK ZONE SIGN	ED	2,250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,732.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,376.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	48.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	90.000
	0102-115-	TYPE III BARRICADE	ED	64.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	6.000
	0104- 10- 3	SEDIMENT BARRIER	LF	365.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	22.000
	0107- 1-	LITTER REMOVAL	AC	172.400
	0107- 2-	MOWING	AC	26.620
	0110- 1- 1	CLEARING & GRUBBING (45631225201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	280.000
	0120- 6-	EMBANKMENT	CY	150.500
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	6.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	188.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	15.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	0.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	15.500

Call Order: 016 Proposal: T7622

ALT	Item	Description	Unit	Quantity
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	1.000
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	2.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	12.000
	0425- 1-359	INLETS, CURB, TYPE P-5, MODIFY	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	5.000
	0425- 4-	INLETS, ADJUST	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0440- 1- 20	UNDERDRAIN, TYPE II	LF	5.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	20.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	28.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	8.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	191.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	80.000
	0527- 2-	DETECTABLE WARNINGS	SF	19.000
	0530- 74-	BEDDING STONE	TN	1.600
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45631225201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	8.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	4.000
	0700- 1-913	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	16.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	16.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	24,796.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45631225201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.012
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.010
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.019
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.019
Section 0003 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	90.000