

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 003	Proposal: T1924	District:01
Counties:	SARASOTA			
Road Name:	SR 776			
Limits:	FROM CHARLOTTE CO LINE TO S OF US 41			
Project(s):	44788215201(*)	Federal Aid No:	D125045B	
Project(s):	45101415201	Federal Aid No:	N/A	
Total Roadway Length:	8.141 Miles	Contract Days:	350	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	8.141 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$16,261,053.00			

Please read the full advertisement

Description:

The improvements under this project consist of milling and resurfacing, raised medians, protected bike lanes, signing and pavement markings, and signalization on SR 776 from Charlotte County Line to South of US 41 in Sarasota County.

Call Order: 003 Proposal: T1924

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44788215201)	LS	1.000
	0101- 1-	MOBILIZATION (45101415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44788215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45101415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	20.000
	0102- 60-	WORK ZONE SIGN	ED	16,586.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	311,070.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,632.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,548.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	700.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	700.000
	0102-115-	TYPE III BARRICADE	ED	700.000
	0104- 10- 3	SEDIMENT BARRIER	LF	82,263.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	270.000
	0107- 1-	LITTER REMOVAL	AC	161.920
	0107- 2-	MOWING	AC	114.060
	0110- 1- 1	CLEARING & GRUBBING (44788215201)	LS	1.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	372,881.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,282.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	30,762.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	30,811.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	4,553.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	3,288.000

Call Order: 003 Proposal: T1924

ALT	Item	Description	Unit	Quantity
	0527- 2-	DETECTABLE WARNINGS	SF	536.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,162.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	8,706.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	20.394
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	13,251.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	888.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,958.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	21.887
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.059
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.355
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	479.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.813
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	573.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.258
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.376
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44788215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45101415201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	22.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	40.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	29.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	72.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	8,706.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	415.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	182.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44788215201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45101415201)	LS	1.000

Call Order: 003 Proposal: T1924

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	13,251.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	913.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,960.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.355
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	477.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	573.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.342
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	4,476.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	180.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	180.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	22.158
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	21.887
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.059
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	15.837
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.258
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	18.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	147.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	21.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	12.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	6.000
	0660- 3- 51	VEHICLE DETECTION SYSTEM- MICROWAVE, ADJUST & MODIFY, CABINET EQUIPMENT	EA	1.000
	0660- 3- 52	VEHICLE DETECTION SYSTEM - MICROWAVE, ADJUST & MODIFY, ABOVE GROUND EQUIPMENT	EA	4.000
	0670- 5-710	TRAFFIC CONTROLLER ASSEMBLY, MODIFY ONLY - NO COMPONENTS ADDED	AS	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000