

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 010	Proposal: T3953	District:03
Counties:	HOLMES			
Road Name:	RICE MACHINE RD			
Limits:	OVER RICE MACHINE BRANCH, BRIDGE NO 524139			
Project(s):	44117615201(*)	Federal Aid No: D326017B		
Total Roadway Length:	0.059 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	12/02/26	
Total Proposal Length:	0.059 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	
Proposal Budget Estimate:		\$793,989.00		

Please read the full advertisement

Description:

The Improvements under this Contract consist of replacing the structurally deficient bridge on Rice Machine Road over Rice Machine Branch (Bridge No. 524139) in Holmes County, Florida with a new concrete bridge culvert (Bridge No. 524236) within its existing alignment. Other improvements included are paved roadway approaches and pavement markings. A project detour will be in place.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 010 Proposal: T3953

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	157.300
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	21,887.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44117615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44117615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	10,004.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,624.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	656.000
	0102-115-	TYPE III BARRICADE	ED	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	524.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	146.000
	0110- 1- 1	CLEARING & GRUBBING (44117615201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,796.500
	0120- 4-	SUBSOIL EXCAVATION	CY	327.100
	0120- 6-	EMBANKMENT	CY	1,343.800
	0160- 4-	TYPE B STABILIZATION	SY	1,023.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	709.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	15.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	81.800
	0440- 1- 50	UNDERDRAIN, TYPE V	LF	312.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	834.000
Section 0003 Signing				
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	16.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.118
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.118