

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250528	Call Order: 009	Proposal: T2991	District:02
Counties:	DUVAL			
Road Name:	SR A1A (US 90A / 3RD ST)			
Limits:	AT 3RD AVE S AND AT 7TH AVE N			
Project(s):	44984215201(*)	Federal Aid No:	D224024B	
Total Roadway Length:	0.150 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	05/28/25	
Total Proposal Length:	0.150 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$2,086,692.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutters, traffic signals, highway signing, sidewalks/bicycle path, and other incidental construction on SR A1A (US 90A) 3rd St at 3rd Ave S and 7th Ave N in Duval County.

Call Order: 009 Proposal: T2991

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44984215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44984215201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44984215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	32.000
	0102- 60-	WORK ZONE SIGN	ED	12,236.000
	0102- 61-	BUSINESS SIGN	EA	8.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	360.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	276.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,266.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	9,536.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	256.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	348.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	1.510
	0107- 2-	MOWING	AC	0.160
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44984215201)	LS	1.000
	0108- 3-	MONITOR EXISTING STRUCTURES- GROUNDWATER MONITORING (44984215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44984215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	227.000

Call Order: 009 Proposal: T2991

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	163.500
	0160- 4-	TYPE B STABILIZATION	SY	195.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	98.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,845.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	64.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	407.800
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	2.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-441	INLETS, CURB, TYPE J-4, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	21.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	30.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	27.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	32.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	372.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	29.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	130.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	60.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	32.000
	0527- 2-	DETECTABLE WARNINGS	SF	118.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	230.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	14.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	80.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	76.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.023
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44984215201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	15.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	4.000
	0700-141-161	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, BLANK OUT SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	4.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	122.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	33.000

Call Order: 009 Proposal: T2991

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44984215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	578.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	358.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	192.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.079
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.059
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	432.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.228
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.108
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.153
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	25.000
Section 0003 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.150
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	215.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	543.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	565.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	96.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	48.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	2.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	8.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	4.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	4.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	4.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	180.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	15.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	72.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000

Call Order: 009 Proposal: T2991

ALT	Item	Description	Unit	Quantity
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	8.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
Section 0004 Utilities				
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (44984215201)	LS	1.000