

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260225	Call Order: 013	Proposal: T4751	District:04
Counties:	PALM BEACH			
Road Name:	SR 704 (OKEECHOBEE BLVD)			
Limits:	FROM E OF SR 809 (MILITARY TR) TO SR 9			
Project(s):	44754515201(*)	Federal Aid No:	D425087B	
Project(s):	45108415201	Federal Aid No:	D425073B	
Project(s):	45108415202	Federal Aid No:	N/A	
Project(s):	45108515201	Federal Aid No:	D425074B	
Total Roadway Length:	3.132 Miles	Contract Days:	203	
Total Bridge Length:	0.000 Miles	Letting Date:	02/25/26	
Total Proposal Length:	3.132 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$2,402,364.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of , but are not limited to, MOT (traffic officer, standard, ped flagger, ped LCD, Arrow Board, PCMS, barricade, signalization, traffic detection), protections (sediment, inlet), earthwork (excavation), asphalt (base, milling, resurfacing), concrete (removal, sidewalk, driveways, curb, curb and gutter), pavement markings (painted, thermoplastic, bike lane, RPM, detectable), signing (single-column, panel, panel remove, object marker), lighting (conductors, luminaire, luminaire and bracket remove, pole complete, pole and foundation remove, cable distribution), signalization (prestressed pole, aluminum pole pedestal, aluminum pole remove, vehicular auxiliaries, ped signal, ped signal remove, ped detector, loop detector/assembly, cable, cable remove), utilities adjustments (manhole, valve box), electrical (power service, service wire, service disconnect), pull/splice box, conduit, fiber optic locator, and sod for 2.408 miles along State Road 704 (Okeechobee Boulevard) from east of State Road 809 (Military Trail) to State Road 9 (I-95) including the intersection of State Road 704 (Okeechobee Boulevard) and State Road 809 (Military Trail), and for 0.200 miles at the intersection of State Road 882 (Forest Hill Boulevard) and Haverhill Road, in Palm Beach County.

Call Order: 013 Proposal: T4751

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44754515201)	LS	1.000
	0101- 1-	MOBILIZATION (45108415201)	LS	1.000
	0101- 1-	MOBILIZATION (45108515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44754515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45108415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45108515201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	1,512.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	288.000
	0102- 60-	WORK ZONE SIGN	ED	12,757.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,426.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	7,739.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	391.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	910.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	406.000

Call Order: 013 Proposal: T4751

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	406.000
	0102-115-	TYPE III BARRICADE	ED	1,808.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,175.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	33.000
	0107- 1-	LITTER REMOVAL	AC	26.630
	0107- 2-	MOWING	AC	21.790
	0110- 1- 1	CLEARING & GRUBBING (44754515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45108515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	297.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3.400
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45108515201)	LS	1.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	61.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	43,564.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,599.100
	0425- 5-	MANHOLE, ADJUST	EA	15.000
	0425- 6-	VALVE BOXES, ADJUST	EA	13.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	260.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	10.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	233.000
	0527- 2-	DETECTABLE WARNINGS	SF	65.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	45.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.062
	0999- 16-	PARTNERING, DO NOT BID (44754515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44754515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45108415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45108515201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (45108415202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	14.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	13.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	8.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	812.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	25.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45108415201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45108515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,910.000

Call Order: 013 Proposal: T4751

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	86.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	568.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.773
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	84.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	12.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.044
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,572.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.686
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.030
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.372
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.242
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	543.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	621.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	14.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	60.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,043.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,086.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	5.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	34.000
	0715- 61-411	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 8' ARM LENGTH	EA	1.000
	0715- 61-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	4.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	38.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	33.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,220.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000

Call Order: 013 Proposal: T4751

ALT	Item	Description	Unit	Quantity
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	203.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	17.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	149.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	23.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	16.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	46.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000