

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT260325 Call Order: 016 Proposal: T3951 District:03  
 Counties: BAY  
 Road Name: SR 20  
 Limits: OVER ECONFINA CREEK, BRIDGE NO 460037 AND 460034  
 Project(s): 44514115201(\*) Federal Aid No: D325031B  
 Total Roadway Length: 0.079 Miles Contract Days: 1120  
 Total Bridge Length: 0.533 Miles Letting Date: 03/25/26  
 Total Proposal Length: 0.612 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Day

Proposal Budget Estimate: \$19,607,353.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of replacing bridges on SR 20 over Econfina Creek, Bridge No. 460037 and 460034 in Bay County. Also included in this Contract is excavation, embankment, stabilization, base construction, pilings, riprap-rubble, approach slabs, bridge substructure and superstructure, constructing and removing Department owned temporary bridges, asphalt placement, safety and drainage improvements, and signing and pavement markings (including placement of thermoplastic markings).

**Call Order: 016 Proposal: T3951**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44514115201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44514115201)	LS	1.000
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	255.600
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	242.600
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	627.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	2,047.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	2,047.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	32.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	130,442.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	30,786.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	41,974.000
	0450- 8- 33	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 18" CARBON STEEL, WIDTH 55-57"	LF	4,002.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	68.000
	0455- 35- 22	STEEL PILING, 24" DIA. PIPE	LF	6,003.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	68.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	10.000
	0455-144- 22	TEST PILES - STEEL, 24" DIA PIPE	LF	1,179.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	188.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,065.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	88.200
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,751.000

**Call Order: 016 Proposal: T3951**

ALT	Item	Description	Unit	Quantity
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	704.000
	0530- 74-	BEDDING STONE	TN	988.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	3,193.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	8.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44514115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44514115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44514115201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44514115201)	LS	1.000
	0102- 2-400	SPECIAL DETOUR- TEMPORARY BRIDGE (Bridge #460170)	LS	1.000
	0102- 2-400	SPECIAL DETOUR- TEMPORARY BRIDGE (Bridge #460171)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	16.200
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	59,008.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	4,356.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	530.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	2,445.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	740.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	105,968.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	24.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,268.000
	0102-115-	TYPE III BARRICADE	ED	10,688.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.155
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.155
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	184.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,801.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	396.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	440.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	430.440
	0107- 2-	MOWING	AC	314.390
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44514115201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44514115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44514115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	311.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	837.900
	0120- 6-	EMBANKMENT	CY	26,778.600
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	13.000
	0145- 3-	GEOSYNTHETIC REINFORCED EMBANKMENT	SY	11,885.000

**Call Order: 016 Proposal: T3951**

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	10,554.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,219.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	824.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	1,830.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	4,320.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,239.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	697.800
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	941.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	86.200
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	9.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	977.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	7.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	0.200
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	328.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	220.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,423.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	270.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	45.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	79.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	125.800
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,639.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, APPROACH TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,437.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	2.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	3,382.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	6,227.000
	0550- 10-410	FENCING, WOOD FENCE, 0.0-5.0'	LF	120.000
	0570- 1- 1	PERFORMANCE TURF	SY	5,129.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	13,296.000
	0571- 1- 13	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 3	SY	5,954.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,752.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.356
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.352
	0917-532- 11	BIOSORPTION ACTIVATED MEDIA, BAM- FILTER STRIP	CY	1,061.800
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44514115201)	LS	1.000
<b>Section 0003 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	1.451
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	20.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000

**Call Order: 016 Proposal: T3951**

ALT	Item	Description	Unit	Quantity
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	155.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44514115201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	144.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	35.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	44.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.142
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.675
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.215
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.155
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.155