

Letting:	CT261202	Call Order: 018	Proposal: T5897	District:05
Counties:	BREVARD			
Road Name:	SR A1A (N ATLANTIC AVE) AND SR 528 (SR A1A)			
Limits:	AT TAYLOR AVE, FROM SR 520 TO GEORGE KING BLVD, FROM W OF SYKES CREEK TO			

Total Roadway Length:	8.146 Miles	Contract Days:	160
Total Bridge Length:	0.300 Miles	Letting Date:	12/02/26
Total Proposal Length:	7.846 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days

The Improvements under this Contract consist of Pedestrian Hybrid Beacon on State Road A1A at Taylor Avenue, approximately 0.423 miles in Brevard County. Milling and Resurfacing on State Road A1A from State Road 520 to George King Blvd., approximately 2.768 miles in Brevard County. Median Guardrail Installation on State Road 528/ State Road A1A from West of Sykes Creek to George King Blvd., approximately 4.955 miles in Brevard County. Milling and Resurfacing on State Road 528 from West of Sykes Creek to SR 401, approximately 4.315 miles in Brevard County.

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45268515201)	LS	1.000
	0101- 1-	MOBILIZATION (45268815201)	LS	1.000
	0101- 1-	MOBILIZATION (45268825201)	LS	1.000
	0101- 1-	MOBILIZATION (45707015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45268515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45268815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45268825201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45707015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	320.000
	0102- 60-	WORK ZONE SIGN	ED	24,220.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	64,344.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	7,545.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	6,544.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	672.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	1,140.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,030.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	800.000

Call Order: 018 Proposal: T5897

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	800.000
	0102-115-	TYPE III BARRICADE	ED	240.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	960.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	960.000
	0104- 10- 3	SEDIMENT BARRIER	LF	33.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	189.000
	0107- 1-	LITTER REMOVAL	AC	850.220
	0107- 2-	MOWING	AC	753.490
	0110- 1- 1	CLEARING & GRUBBING (45268825201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45707015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	120.000
	0120- 1-	REGULAR EXCAVATION	CY	1,318.000
	0120- 6-	EMBANKMENT	CY	777.000
	0160- 4-	TYPE B STABILIZATION	SY	1,393.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	933.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	9,824.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	149,942.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	5,793.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	53,198.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	16,458.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	1,397.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	24,681.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	12,598.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	3,277.600
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	15,566.300
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	102.700
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,976.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	8,297.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2,488.400
	0425- 1-505	INLETS, DT BOT, TYPE A, PARTIAL	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	3.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	15.000
	0425- 6-	VALVE BOXES, ADJUST	EA	22.000
	0425- 6- 1	METER BOXES, ADJUST	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	26.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	158.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	38.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	7.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	64.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	101.000
	0527- 2-	DETECTABLE WARNINGS	SF	120.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	675.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	21,950.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	21,950.000

Call Order: 018 Proposal: T5897

ALT	Item	Description	Unit	Quantity
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	102.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	3.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,550.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 29	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	5.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	37,264.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	160.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (45268825201)	LS	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	8.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	8.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	3.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45268515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45268815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45268825201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45707015201)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	7.078
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	27.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	100.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	20.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,999.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45268515201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45268815201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45268825201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,149.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,632.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	394.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.862
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	111.000

Call Order: 018 Proposal: T5897

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,069.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.794
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,083.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.917
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.431
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	8.251
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	7.919
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.898
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.034
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.188
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.957
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.688
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.654
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.688
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.652

Section 0003 Signalization

	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	229.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	298.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	35.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	210.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	32.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	8.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	2.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	1.000
	0684- 7- 1	MANAGED HUB ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000

Call Order: 018 Proposal: T5897

ALT	Item	Description	Unit	Quantity
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	1.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	1.000
	0700-141-160	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, BLANK OUT SIGN <12 SF	EA	1.000