

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250528	Call Order: 013	Proposal: T3933	District:03
Counties:	WAKULLA			
Road Name:	SR 369 (US 319)			
Limits:	FROM US 319 NB OFF RAMP TO S OF E IVAN RD			
Project(s):	41931525201(*)	Federal Aid No:	D324035B	
Project(s):	41931525202	Federal Aid No:	D324035B	
Total Roadway Length:	3.181 Miles	Contract Days:	330	
Total Bridge Length:	0.000 Miles	Letting Date:	05/28/25	
Total Proposal Length:	3.181 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$3,703,038.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of FPID Nos. 419315-2-52-01 and 419315-2-52-02 consist of but are not limited to, asphalt (milling, resurfacing, travel and turn lanes, side streets, crossovers, shoulders, driveways), drainage (inlets, pipe culvert, manhole, MES), concrete (removal, curb ramp, curb and gutter, sidewalk), MOT (standard, barrier, PCMS), protections (sediment, inlet), earthwork (excavation, embankment), utility adjustments (manhole, valve box), signing (single-column, multi-column), pavement markings (RPM, painted, thermoplastic), signal (conduit, ped pole, pull boxes, loop detectors), lighting (intersection retrofit), and sod along State Road 369 from US 319 NB Off Ramp (MP 0.000) to south of East Ivan Road (MP 3.181) for 3.181 miles in the City of Crawfordville, Wakulla County.

Call Order: 013 Proposal: T3933

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (41931525201)	LS	1.000
	0101- 1-	MOBILIZATION (41931525202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41931525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41931525202)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	14.800
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	76.000
	0102- 60-	WORK ZONE SIGN	ED	34,350.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	154,790.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,150.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	390.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,024.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	990.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	990.000
	0102-115-	TYPE III BARRICADE	ED	2,000.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,085.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	266.290
	0107- 2-	MOWING	AC	215.380
	0110- 1- 1	CLEARING & GRUBBING (41931525201)	LS	1.000

Call Order: 013 Proposal: T3933

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (41931525202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	58.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	654.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	419.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (41931525202)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	2,122.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,777.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	75,466.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	17,813.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	144.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	144.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	9,771.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10' (41931525202)	EA	3.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD (41931525202)	LF	477.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	333.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	74.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	160.000
	0527- 2-	DETECTABLE WARNINGS	SF	244.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,979.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,736.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	21.036
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	103.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	327.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	5.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	21.036
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41931525201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41931525202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	61.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	7.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	45.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	2.000

Call Order: 013 Proposal: T3933

ALT	Item	Description	Unit	Quantity
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	16.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,813.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41931525201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.087
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,388.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	130.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	658.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.563
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	148.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	821.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,148.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	18.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	18.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.977
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.372
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.332
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	663.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	627.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	60.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	27.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	200.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	5,109.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 61-252	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 15' ARM LENGTH	EA	8.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	3.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	11.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	668.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	574.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000

Call Order: 013 Proposal: T3933

ALT	Item	Description	Unit	Quantity
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	21.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	22.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	10.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	17.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	22.000
	0660- 1-105	LOOP DETECTOR, INDUCTIVE, F&I, TYPE 5, 2CHANNEL, SOLID STATE, SHELF MOUNTED	EA	12.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	22.000