

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	07260204	Call Order: 003	Proposal: E7U47-R0	District:07
Counties:	DIST/ST-WIDE			
Road Name:	DISTRICTWIDE GROUND MODIFICATION			
Limits:	Midpoint			
Project(s):	41912715219(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	02/04/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	N/A	

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

**Description:**

The work under this Contract consists of providing both non-emergency and emergency subsurface ground repairs on District 7 roadways impacted by sinkholes and/or voids resulting from stormwater pipe damage. The Contractor will be required to have immediate access to all materials, equipment, and labor required to initiate and perform repairs with continuous operations as directed in the work document issued by the Department.

Contractors must submit with their bid the "Experience in Sinkhole Remediation & Stabilization" Experience Form or be Prequalified in Sinkhole Remediation & Stabilization.

The contract will be awarded at the Department's Advertised Project Cost amount of \$1,000,000.00; low bid will set the unit price.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Note the Substituted Commercial General Liability Insurance requirements contained in section(s) 7-13.2 and 7-13.4 of the project Specifications.

Previous Contract E7P91, let 1/11/2023.

**Call Order: 003 Proposal: E7U47-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	10.000
	0102- 60-	WORK ZONE SIGN	ED	300.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	25.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	20.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	280.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	20.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	40.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	100.000

**Call Order: 003 Proposal: E7U47-R0**

ALT	Item	Description	Unit	Quantity
	0102-115-	TYPE III BARRICADE	ED	28.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	20.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	15.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	80.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	10.000
	0160- 4-	TYPE B STABILIZATION	SY	120.000
	0173- 71-	DRILLING HOLES FOR PRESSURE GROUTING	EA	200.000
	0173- 76-	GROUT PIPE INSTALLATION	LF	3,000.000
	0173- 77- 3	SUBSURFACE PRESSURE GROUTING, CEMENT SLURRY	CY	250.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	300.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	150.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	150.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	150.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	150.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	150.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	150.000
	0327- 70- 10	MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH	SY	150.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	150.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	150.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	20.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	30.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	20.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	15.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	15.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	20.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	30.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	25.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	15.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	10.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	50.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	35.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	20.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	80.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	80.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	80.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.000

**Call Order: 003 Proposal: E7U47-R0**

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	10.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	60.000
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	70.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	60.000
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"	GM	2.000
	0906-173-100	SINGLE COMPONENT POLYURETHANE INJECTION	GA	2,500.000
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	70.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E102- 20-	PORTABLE LIGHTING UNIT (MAST MOUNTED)	ED	2.000
	E102- 74- 9	TRAFFIC CONES	ED	300.000
	E102- 97- 1	TRUCK MOUNTED ATTENUATOR (TEMPORARY)	ED	2.000
	E710- 11-121	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	LF	180.000
	E710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	LF	350.000
	E710- 11-221	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	LF	400.000
	E710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	LF	350.000