

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 009	Proposal: T3937	District:03
Counties:	JACKSON			
Road Name:	CR 278 (PEACOCK BRIDGE RD)			
Limits:	OVER CHIPOLA RIVER, BRIDGE NO 530026			
Project(s):	44905515201(*)	Federal Aid No: D326021B		
Total Roadway Length:	0.760 Miles	Contract Days:	485	
Total Bridge Length:	0.060 Miles	Letting Date:	09/30/26	
Total Proposal Length:	0.820 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$9,035,014.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of roadway and pavement reconstruction, guardrail, drainage improvements, removal of existing bridge No. 530026, construction of new bridge No. 534203, signing and pavement markings on CR 278 Peacock Bridge Road over Chipola River Bridge No. 530026 in Jackson County.

Call Order: 009 Proposal: T3937

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44905515201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	455.900
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	95.300
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	141.800
	0400- 7- 1	BRIDGE DECK GROOVING	SY	1,573.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	1,573.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	9.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	78,205.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	25,286.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	17,916.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	1,999.000
	0455- 88- 4	DRILLED SHAFT, 42" DIA	LF	831.000
	0455-107- 4	DRILLED SHAFT CASING, 42" DIAMETER	LF	218.000
	0455-111-	CORE-PILOT HOLE, DRILLED SHAFT EXCAVATION	LF	836.000
	0455-122- 4	EXCAVATION UNCLASSIFIED SHAFT, 42" DIA	LF	710.000
	0455-147- 1	THERMAL INTEGRITY TESTING, UP TO 4' SHAFT DIAMETER	EA	12.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	83.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	820.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	41.700
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,294.700
	0530- 74-	BEDDING STONE	TN	854.300
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	2,460.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	6.000

Call Order: 009 Proposal: T3937

ALT	Item	Description	Unit	Quantity
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44905515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44905515201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44905515201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44905515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	41.200
	0102- 60-	WORK ZONE SIGN	ED	8,412.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,100.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	26,582.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	6.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	998.000
	0102-115-	TYPE III BARRICADE	ED	220.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	200.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,016.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	320.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	711.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44905515201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44905515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44905515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	130.000
	0120- 1-	REGULAR EXCAVATION	CY	17,362.000
	0120- 4-	SUBSOIL EXCAVATION	CY	320.000
	0120- 6-	EMBANKMENT	CY	44,042.000
	0145- 1-	GEOSYNTHETIC REINFORCED SOIL SLOPE	SF	1,883.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	1,612.000
	0160- 4-	TYPE B STABILIZATION	SY	13,187.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,115.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	8,221.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	66.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	3,934.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	851.100
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	1,031.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	51.400
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	7.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	185.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	88.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	37.000

Call Order: 009 Proposal: T3937

ALT	Item	Description	Unit	Quantity
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	6.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,021.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	9.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	31.600
	0530- 74-	BEDDING STONE	TN	18.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,334.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,859.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 1	PERFORMANCE TURF	SY	11,583.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	19,325.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,027.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.659
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	24.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.691
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	216.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44905515201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	33.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.481
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.506
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.133
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.133