

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 002	Proposal: T1917	District:01
Counties:	HIGHLANDS			
Road Name:	SR 17			
Limits:	FROM S OF CR 17 (KENILWORTH BLVD) TO E OF SR 25 (US 98 / US 27)			
Project(s):	44917715201	Federal Aid No:	D125055B	
Project(s):	45126215201(*)	Federal Aid No:	D125046B	
Project(s):	45126215202	Federal Aid No:	D125046B	
Total Roadway Length:	11.026 Miles	Contract Days:	250	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	11.157 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$10,555,843.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, drainage improvements, curb and gutter, sidewalk, signalization, lighting, rail crossing reconstruction, and signing and pavement markings on SR 17 from South of CR 17 (Kenilworth Blvd) to E of SR 25 (US 98 / US 27) and from South of Lake Verona Blvd to South of Delaney Ave in Highlands County.

Railroad Insurance Required

Call Order: 002 Proposal: T1917

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44917715201)	LS	1.000
	0101- 1-	MOBILIZATION (45126215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44917715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45126215201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45126215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,070.000
	0102- 60-	WORK ZONE SIGN	ED	23,981.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,790.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,310.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	714.000
	0102-115-	TYPE III BARRICADE	ED	810.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,653.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	284.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	139.000
	0107- 1-	LITTER REMOVAL	AC	447.090
	0107- 2-	MOWING	AC	446.390
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44917715201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (45126215201)	LS	1.000

Call Order: 002 Proposal: T1917

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44917715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45126215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	944.000
	0120- 1-	REGULAR EXCAVATION	CY	7.900
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	622.000
	0120- 6-	EMBANKMENT	CY	116.600
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44917715201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	829.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	566.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	260,167.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	360.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	21,625.100
	0400- 2- 8	CONCRETE CLASS II, BULKHEAD	CY	48.500
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	7,001.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	2.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	4.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	28.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	13.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	34.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	39.000
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	48.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	2,912.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,444.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	88.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	358.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	401.000
	0527- 2-	DETECTABLE WARNINGS	SF	2,862.000
	0530- 4- 9	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 9"	SY	79.000
	0570- 1- 1	PERFORMANCE TURF	SY	868.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	24,690.000
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (45126215201)	LS	1.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	32.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.021
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44917715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45126215201)	LS	1.000

Call Order: 002 Proposal: T1917

ALT	Item	Description	Unit	Quantity
	1050- 42-106	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, CASING/CONDUIT, 6"	LF	8.000
Section 0002 Signing				
	0654- 2- 28	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR	AS	12.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	21.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	13.000
	0700- 1-912	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-913	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-914	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 30.1+ SF	EA	1.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	11.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,631.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45126215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	5,986.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	6,571.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	4,281.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.746
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	40.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	83.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	3,273.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.115
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	324.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,924.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	44.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	26.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	364.000

Call Order: 002 Proposal: T1917

ALT	Item	Description	Unit	Quantity
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	386.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.032
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.041
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	22.625
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.257
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.699
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	22.109
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.906
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	338.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,580.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	44.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	8.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	176.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	8.000
	0641- 2- 30	PRESTRESSED CONCRETE POLE, INSTALL	EA	8.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	7,652.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	0715- 7- 12	LOAD CENTER, F&I, PRIMARY VOLTAGE	EA	8.000
	0715- 61-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	11.000
	0715- 61-142	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 12' ARM LENGTH	EA	4.000
	0715- 61-311	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	18.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45126215202)	LS	1.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,002.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,480.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	6.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	86.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	26.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	16.000
	0650- 1- 11	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	10.000

Call Order: 002 Proposal: T1917

ALT	Item	Description	Unit	Quantity
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	12.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	30.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	24.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	9.000
	0660- 1-106	LOOP DETECTOR INDUCTIVE , F&I, TYPE 6, 2 CH,SS,S,TD	EA	13.000
	0660- 1-112	LOOP DETECTOR INDUCTIVE, F&I, TYPE 12, 4 CH, SS, RM, TD	EA	25.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	11.000
	0660- 2-105	LOOP ASSEMBLY, F&I, TYPE E	AS	2.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	25.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	28.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	6.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	6.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000