

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250924	Call Order: 008	Proposal: T4741	District:04
Counties:	BROWARD			
Road Name:	SR 814 (ATLANTIC BLVD)			
Limits:	AT LYONS RD			
Project(s):	44755015201(*)	Federal Aid No: D425054B		
Total Roadway Length:	0.436 Miles	Contract Days:	133	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	0.436 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$1,027,765.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Sr-814/Atlantic Blvd. at Lyons Rd. intersection improvement project, which includes the extension of the right turn lane on Atlantic Blvd and the extension of the dual left turn lanes at Lyons Rd.

Call Order: 008 Proposal: T4741

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44755015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44755015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,453.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,950.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	266.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	294.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,743.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0110- 1- 1	CLEARING & GRUBBING (44755015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	470.000
	0110- 21-	TREE PROTECTION BARRIER	LF	60.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	616.000
	0120- 6-	EMBANKMENT	CY	0.600
	0160- 4-	TYPE B STABILIZATION	SY	780.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	780.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,189.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	323.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	284.300
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-359	INLETS, CURB, TYPE P-5, MODIFY	EA	1.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	5.000

Call Order: 008 Proposal: T4741

ALT	Item	Description	Unit	Quantity
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	148.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	49.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	534.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	247.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	168.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	331.000
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (44755015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44755015201)	LS	1.000
Section 0002 Signing				
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	76.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44755015201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.045
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.086
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	10.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.343
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.291
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.017
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.117
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	778.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	13.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,800.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	37.000
	0715- 61-311	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 8' ARM LENGTH	EA	5.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	5.000
Section 0004 Landscape / Peripheral				
	0581- 1-300	RELOCATE TREES AND PALMS, TREE, LESS THAN OR EQUAL TO 3.0" DBH	EA	3.000
	0581- 1-360	RELOCATE TREES AND PALMS, TREE, 16.1" OR GREATER DBH	EA	1.000