

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	07250813	Call Order: 001	Proposal: E7Q69	District:07
Counties:	PINELLAS			
Road Name:	US 19/SR 55 - RESURFACING			
Limits:	15150000			
Project(s):	45128715201(*)	Federal Aid No:	N/A	
Total Roadway Length:	11.491 Miles	Contract Days:	210	
Total Bridge Length:	0.000 Miles	Letting Date:	08/13/25	
Total Proposal Length:	11.491 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days Acquis.	
Proposal Budget Estimate:	\$12,522,030.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of pavement only project including the milling and resurfacing of friction course, longitudinal grooving, pavement markings, traffic monitoring sites, and other incidental construction on SR 55 (US 19) from S. of Tampa Rd. to S. of Live Oak St. in Pinellas County.

Prequalification required.

Call Order: 001 Proposal: E7Q69

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45128715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45128715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,100.000
	0102- 60-	WORK ZONE SIGN	ED	32,214.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	60,711.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	630.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,351.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,680.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,680.000
	0102-115-	TYPE III BARRICADE	ED	350.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	420.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	420.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	83.000
	0107- 1-	LITTER REMOVAL	AC	397.810
	0107- 2-	MOWING	AC	300.910
	0110- 1- 1	CLEARING & GRUBBING (45128715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	8.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	432,998.000
	0328- 1-	ASPHALT PAVEMENT GROOVING	SY	7,943.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,823.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	33,896.300
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	7.000

Call Order: 001 Proposal: E7Q69

ALT	Item	Description	Unit	Quantity
	0527- 2-	DETECTABLE WARNINGS	SF	83.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	13,109.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	168.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	24.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	12,083.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	17.140
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	3.681
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	6,830.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,936.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,726.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	31.711
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.214
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	3.586
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	650.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	11.796
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	546.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.975
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45128715201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	8.823
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	12,083.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	941.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45128715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,830.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,936.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,726.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	3.586
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	650.000

Call Order: 001 Proposal: E7Q69

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	546.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.975
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	6,611.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	25.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	25.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	17.140
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	3.681
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	31.711
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.214
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	11.796
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	628.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	210.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	104.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	6.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	114.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	61.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	8.000