

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT260520 Call Order: 010 Proposal: T4737 District:04  
 Counties: BROWARD, PALM BEACH  
 Road Name: SR 9 (I-95) AND SR 862 (I-595)  
 Limits: AT VARIOUS LOCATIONS AS SHOWN IN THE PLANS  
 Project(s): 45159715201(\*) Federal Aid No: D426024B  
 Project(s): 45159815201 Federal Aid No: D426025B  
 Total Roadway Length: 1.840 Miles Contract Days: 213  
 Total Bridge Length: 0.000 Miles Letting Date: 05/20/26  
 Total Proposal Length: 1.840 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Days  
 Proposal Budget Estimate: \$3,733,630.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of, but are not limited to, MOT (standard, PCMS, barricade), asphalt (milling, resurfacing), signing (single-column, sign strip, enhanced, panel), pavement markings (RPM, painted, thermoplastic), ITS (subsurface and location documentation, cabinet, field ethernet, WWDS), conduit (above-ground, directional bore), fiber optic (cable, connection, locate), pull/splice box, junction box, electrical service (wire, disconnect, power, uninterruptible, remote management), prestressed pole, at eleven Interstate exit ramps along State Road 9 (I-95) and State Road 84 (I-595/Port Everglades Expressway) for a total of 3.205 miles in the City of Fort Lauderdale, the City of Pompano Beach, and the Town of Davie, Broward County, and in the City of Boca Raton and the City of West Palm Beach, Palm Beach County.

**Call Order: 010 Proposal: T4737**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (45159715201)	LS	1.000
	0101- 1-	MOBILIZATION (45159815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45159715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45159815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,892.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,404.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	342.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	188.000
	0102-115-	TYPE III BARRICADE	ED	188.000
	0107- 1-	LITTER REMOVAL	AC	133.480
	0107- 2-	MOWING	AC	107.690
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	8,543.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	472.800
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	472.800
	0999- 16-	PARTNERING, DO NOT BID (45159715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45159715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45159815201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	20.000

**Call Order: 010 Proposal: T4737**

ALT	Item	Description	Unit	Quantity
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	24.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	22.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	16.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	11.000
	0700-141-440	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I BARRIER SIDE MOUNT, HIGHLIGHTED SIGN <12 SF	EA	1.000
	0700-142-140	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	7.000
	0700-142-240	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I BARRIER TOP MOUNT, HIGHLIGHTED SIGN <12 SF	EA	3.000
	0700-142-440	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I BARRIER SIDE MOUNT, HIGHLIGHTED SIGN <12 SF	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,066.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45159715201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45159815201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	24.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	97.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.702
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.152
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.400
<b>Section 0003 Intelligent Transportation System</b>				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	3.205
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	11.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	13,531.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	386.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	17,251.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	192.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	2.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	7.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	12.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	5.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	213.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	67.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	40.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	1.000

**Call Order: 010 Proposal: T4737**

ALT	Item	Description	Unit	Quantity
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	5,741.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	12.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	10.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	12.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	3.000
	0660- 7- 22	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED	EA	8.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	12.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	12.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	12.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	12.000